



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

Property of  
Flood Control District of MC Library  
Please Return to  
2891 W. Durango  
Phoenix, AZ 85009

Maricopa County Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009

June 16, 1986

Attn: Nick Karan, P.E.  
Chief, Engineering Division

Re: Shrinkage Testing  
Spookhill Flood Retention Structure  
Maricopa County, Arizona

Job No. 2125J296

According to your request, we have completed the field sampling and laboratory testing services for the existing Spookhill Flood Retention Structure. These services were performed in accordance with your contract FCD 85-45 dated January 20, 1986.

The purpose of this investigation was to obtain disturbed and relatively undisturbed soil samples from various depths in the existing embankment for shrinkage limits testing. The subsurface exploration and sampling were performed at Station 265+00 and Station 280+00 along the Spookhill Flood Retention Structure. The shrinkage limits tests were run according to the procedures provided by the Soil Conservation Service. A copy of these procedures is included in the Appendix.

Subsurface exploration at the site was accomplished with a backhoe and an auger drill rig. The backhoe was used for the shallower exploration where block samples were taken, and the auger drill rig was used for the deeper exploration where Dennison samples were

obtained. The block samples were approximately 1 foot to a side, and the Dennison samples were approximately 2 feet long and 6-1/2 inches in diameter.

The predominant embankment material encountered was silty sand with varying amounts of gravel. Clayey sand with low plasticity was encountered in Boring 1 from a depth of 2 feet to a depth of 15 feet. This clayey sand was underlain by silty sand. The surface soils at both sites were sand and gravel to a depth of 2 feet. Logs of Borings are included in the Appendix.

Shrinkage limits tests as described by the SCS procedures could be performed with the remolded samples, but they could not be performed with the undisturbed samples. The lack of cohesion and the gravel size particles in the undisturbed samples did not allow the samples to be trimmed to regular shapes that could be measured for volume calculations. Attempts were made to seal the undisturbed samples in cellophane and paraffin to obtain submersed volume measurements. This method did not produce acceptably accurate results because the cellophane and paraffin could not be made to conform well enough to the shape of a trimmed sample.

The remolded samples were prepared in accordance with the design specifications for the fill. This data was provided by the Maricopa County Flood Control district and is reproduced in the Appendix (Construction Monitoring Test Results) along with the specific gravity determinations (Physical Properties). The remolded shrinkage limits tests were run with material passing the #4 sieve. The results of these tests are presented in the following table.



<u>Station</u>	<u>Depth (ft)</u>	<u>Initial Dry Density (pcf)</u>	<u>Initial Moisture Content (%)</u>	<u>Volume Change<sup>1</sup> After Drying (%)</u>
265+00	6.6-7.6	112.5	7.4	+2.7
265+00	9.2-10.2	120.2	8.5	+1.4
265+00	16.2-18.2	121.0	8.0	-0.4
265+00	18.3-20.3	115.7	9.6	-0.4
265+00	20.3-22.3	124.5	8.4	+0.5
280+00	5.5-6.5	118.2	8.6	+3.0
280+00	12.0-13.0	125.3	10.1	+0.5
280+00	16.0-18.0	119.9	9.7	+0.2
280+00	18.0-20.0	119.3	11.0	+0.4
280+00	20.5-22.5	123.6	11.0	+0.6

<sup>1</sup> + indicates volume increase, - indicates volumes decrease.

The volume changes indicate that the soils have a tendency to increase in volume, not shrink upon drying. Irregularities in the samples and measuring techniques are probably responsible for the apparent increase in volume upon drying. A variance of 0.01 inch in the length and diameter measurements would change the volume by 0.7 percent, and a variance of 0.02 inch would affect the volume by 1.4 percent. The individual measurements for each sample varied within ranges from 0.01 inch to 0.05 inch. Accordingly, volume determinations can be expected to vary approximately one percent or slightly more. With this in mind, only two samples exhibited any significant change in volume upon drying. These samples showed volume increases of 2.7 and 3.0 percent. A combination of measurement errors and sample irregularities may be responsible for the apparent volume increase of these two samples.

The sampling and testing program of the Spookhill Flood Retention Structure embankment material indicates that the silty sands and clayey sands used for construction have very low if any remolded



shrinkage potential. Shrinkage limits tests on undisturbed samples were not possible but do not seem necessary in light of the test results on the remolded samples.

We have enjoyed providing these services for you and are prepared to assist in other aspects of this project as needed. If you have any question concerning this report, or if we may be of any additional service, please call us.

Sincerely,  
WESTERN TECHNOLOGIES INC.

Frank Costello, P.E.

jh

Copies to: Addressee (5)



  
Reviewed by: Kenneth L. Ricker, P.E.





APPENDIX

BORING LOG NOTES	A-1
LOGS OF BORINGS	A-2
SCS SHRINKAGE LIMITS PROCEDURES	A-4
PHYSICAL PROPERTIES	A-11
CONSTRUCTION MONITORING TEST RESULTS	A-12
EXPLORATION PHOTOGRAPHS	A-13



BORING LOG NOTES

The number shown in "LOG OF BORING NO." refers to the approximate location of the same number indicated on the "Site Plan" as positioned in the field by the client.

"STA" refers to the approximate stationing of the boring along the embankment.

"TYPE/SIZE BORING" refers to the exploratory equipment used in the boring wherein HSA = hollow-stem auger and 16" bucket = backhoe pit.

"Sample Type" refers to the form of sample recovery, in which B = Block sample and D = Dennison sample.

"Dry Density, pcf" refers to the laboratory-determined dry density in pounds per cubic foot. The symbol "NR" indicates that no sample was recovered. The symbol "\*" indicates that determination of dry density was not possible.

"Unified Classification" refers to the soil type as defined by "Method of Soil Classification". The soils were classified visually in the field and, where appropriate, classifications were modified by visual examination of samples in the laboratory and/or by appropriate tests.

These notes and boring logs are intended for use in conjunction with the purposes of our services defined in the text. Boring log data should not be construed as part of the construction plans nor as defining construction conditions.

Boring logs depict our interpretations of subsurface conditions at the locations and on the date(s) noted. Variations in subsurface conditions and soil characteristics may occur between borings. Groundwater levels may fluctuate due to seasonal variations and other factors.

In general, terms and symbols on the boring logs conform with "Standard Definitions of Terms and Symbols Relating to Soil and Rock Mechanics" (ASTM D653).



**LOG OF BORING NO. 1 Sta. 265+00**

Project Geotechnical Services - Spookhill Dam Job No. 2125J296  
 Elevation Not Determined Datum Crest of the Embankment  
 Type/Size Boring 16" Bucket/7" HSA Rig Type John Deere 510/CME 75  
 Groundwater Conditions None Encountered Date /18/86; 3/18/86

Depth, feet	Sample Interval (ft)		Sample Type	Dry Density pct	Water Content, %	Unified Classification	Description
	Top	Bottom					
						SP-GP	SAND AND GRAVEL FILL; some cobbles, trace silt and clay, greenish gray, medium dense, damp
5						SC	CLAYEY SAND FILL; with silt, some gravel, brown, dense to very dense, damp to slightly damp
	6.6						Finer gravel
		7.6	B	*	7.2		
10	9.2						Light brown, slightly higher moisture content
		10.2	B	*	6.6		
							Brown, slightly more clay
15							Grades into silty sand and gravel
	16.2					SM	SILTY SAND AND GRAVEL FILL; grayish green, very dense, slightly damp
		18.2	D	*	7.8		Some cobbles (granitic composition)
	18.3						
20	20.3		D	*	9.2		
	20.3						
		22.2	D	*	8.4		
	22.2	23.0	D	NR			
25							Sampler refusal @ 23 feet on large cobbles
30							



**LOG OF BORING NO. 2 Sta. 280+00**

Project Geotechnical Services - Spookhill Dam Job No. 2125J296  
 Elevation Not Determined Datum Crest of the Embankment  
 Type/Size Boring 16" Bucket/7" HSA Rig Type John Deere 510/CME 75  
 Groundwater Conditions None Encountered Date 2/18/86; 3/20/86

Depth, feet	Sample Interval (ft)		Sample Type	Dry Density pcf	Water Content, %	Unified Classification	Description
	Top	Bottom					
						SP-GP	SAND AND GRAVEL FILL; trace cobbles, trace silt and clay, greenish gray, medium dense, damp
5	5.5	6.5	B	*	5.8	SM	SILTY SAND FILL; with gravel, trace clay, brown, dense to very dense, damp to slightly damp  Grayish green color, no plasticity
10	12.0	13.0	B	*	5.9		
15	16.0	18.0	D	*	7.9		
18.0	18.0	20.0	D	*	8.6		
20	20.5	22.5	D	*	9.1		
22.5	22.5	23.0	D	NR			
						SM	GRAVELLY SAND; with silt, tan to off white, very dense, slightly damp, very heavy cementation encountered at 22.0 feet
25							Sampler refusal @ 23.0 feet on heavily cemented gravelly sands
30							





50  
R.P.

Subject: ENG - Soil Mechanics - Shrinkage Limits

Date: February 26, 1985

To: Ralph Arrington, State Conservation Engineer,  
SCS, Phoenix, Arizona

File Code:

Attached is a letter from the Lincoln Laboratory indicating the procedure for making shrinkage limits on compacted soils. The letter does not give the instructions I was hoping for but should be sufficient with the following additions:

1. Prepare a compacted specimen using soil from the same area of the fill an undisturbed sample was obtained. Prepare the sample in accordance with the ASTM Standard test procedure used for design of the fill. The dry density and moisture content shall be in accordance with the design specifications for the fill.
2. Extrude the specimen and dry according to the instructions in the attached letter. Determine  $G_s$  and moisture content of the soil.
3. Determine the volume of the mold in accordance with section 3.1.3 ASTM D698.
4. After the specimen has been dried, determine the average diameter, height and volume. The average of the diameter, height and volume shall be calculated from at least six diameter and three height measurements made to the nearest 0.001 in. (0.02 mm).
5. Make shrinkage calculations in accordance with attached letter.
6. Obtain an undisturbed sample of the fill. Determine  $G_s$  and moisture content for the sample.
7. Determine the average diameter, height and volume using measurement procedures similar to item 4.
8. Dry the undisturbed sample according to the attached letter.
9. Determine the average diameter, height and volume using measurement procedures similar to item 4.



10. Make shrinkage calculations in accordance with attached letter.
11. Plot the moisture contents and shrinkage limits percent vs. the dry density values for the remolded and undisturbed samples.
12. Calculate the theoretical minimum volume possible for the soil by using the following equation:

$$V_{\min} = \frac{(W_s)(SL)}{\gamma_w} + \frac{W_s}{G_s \gamma_w}$$

where  $W_s$  = W+ of solids

SL = Shrinkage limit at Placement density in decimal.

13. Calculate volume associated with the in place density and assume one for the placement density volume.
14. Evaluate the volumetric shrinkage to determine the amount completed since construction and what is left yet to reach a minimum volume.
15. Following is an example set of calculations and comparison:

a. Placement density = 1.83 gm/cc

b. Present in place density = 1.87 gm/cc

c.  $G_s = 2.949$  and SL = 19%

d.

$$V_{\min} = \frac{(1.83)(.19)}{1} + \frac{1.83}{(2.949)} = 0.9683$$

e.

$$\gamma_{d_{\max}} = \frac{W_s}{V_{\min.}} = \frac{1.83}{.9683} = 1.89 \text{ gm/cc}$$

f.

$$\gamma = \frac{W_s}{V} \quad V = \frac{W_s}{\gamma} = \frac{1.83}{1.87} = 0.9786 \text{ ft}^3$$



g.


Condition	$\gamma_d$	$W_B$	Vol.	* Min. Vol. Sh.
Constructed	1.83	1.83	1.000	
Present	1.87	1.83	0.9786	
Min. Vol.	1.89	1.83	0.9683	7.2%

$$* \frac{1.0 - .9683}{1.0 - .9786} = \frac{x}{22-12} \quad x = 14.8 \quad A = 22-14.8 = 7.2$$

h.

$$\% C = \frac{1.0 - .9786}{1.0 - .9683} \times 100 = 67.5\% = \text{Amount of Vol. Shrinkage that has occurred to date.}$$

i. Plot of data and resulting calculations.



Ralph Arrington  
February 26, 1985

4

If I can be of further assistance please let me know.

*C.E. Deal for*

CLIFTON E. DEAL  
Soil Mechanics Engineer

Attachment

cc:

Susanne Leckband, Design Engineer,  
SCS, Phoenix, Arizona

Verne Bathurst, State Conservationist,  
SCS, Phoenix, Arizona

Jack C. Stevenson, Head, Engineering Staff, WNTC





Subject: ENG - Soil Mechanics - Shrinkage Limits,  
Volumetric Shrinkage and Lineal Shrinkage

Date: February 12, 1985

To: Clifton E. Deal  
Soil Mechanics Engineer  
WNTC, SCS, Portland, OR

File Code: 210-22

Shrinkage limits, volumetric shrinkage and lineal shrinkage on puddled soils using the procedure of ASTM D427 are highly dependent on how much moisture the soil contains at the start and have little direct application for determining the shrinkage characteristics of a compacted soil. Better predictions can be made for compacted soil by compacting the soil at the proposed placement moisture and making direct volume and density measurements before and after drying to a constant volume.

The soil must be dried slowly and carefully to avoid drying cracks from forming that will affect the actual volume of the dried specimen. A moist room can be used for the initial drying to prevent cracking. Usually, several days are required in the moist room. An alternate method of drying is to place the newly compacted specimens in sealed plastic bags and open the plastic bags for a few minutes at a time several times a day until the bags can be left open to dry at room temperature without cracking. Final drying in a standard oven should continue until no further moisture loss is obtained.

The following relationships are used to calculate the shrinkage properties.

$$V_{SH} = \frac{V_i - V_f}{V_f} \times 100$$

$$L.S. = \left( 1 - \sqrt[3]{\frac{100}{V_{SH} + 100}} \right) \times 100$$

$$S.L. = w_{sat} = \frac{G_s - \gamma_{df}}{G_s \times \gamma_{df}} \times 100$$

Where:

$V_{SH}$  = Volumetric shrinkage

$V_i$  = Initial volume

$V_f$  = Final volume

L.S. = Lineal shrinkage

S.L. = Shrinkage limit

$\gamma_{df}$  = Final dry density

$G_s$  = Specific gravity of soil



For soil specimens with shapes that are not conducive to accurate measurements with a ruler, the relationships can be determined using densities determined by displacement methods such as coating the soil with wax and determining volume by the difference of the weights of the soil in air and in water.

The volumetric shrinkage relationship and the density relationships are derived as follows:

Volume shrinkage is defined as the change in volume divided by the final volume.

$$\begin{aligned}
 V_{SH} &= \frac{V_i - V_f}{V_f} \times 100 \stackrel{(+V_i)}{=} 100 \left[ \frac{\frac{V_i - V_f}{V_i}}{\frac{V_f}{V_i}} \right] \stackrel{\text{Regroup}}{=} 100 \left[ \frac{\frac{V_i - V_f}{V_i}}{\frac{1}{V_i}} \right] \stackrel{\text{Rearrange Terms}}{=} \\
 &= 100 \left[ \frac{\frac{1}{V_f} - \frac{1}{V_i}}{\frac{1}{V_i}} \right] \stackrel{(\times W_{fd})}{=} 100 \left[ \frac{\frac{W_{fd}}{V_f} - \frac{W_{fd}}{V_i}}{\frac{W_{fd}}{V_i}} \right] \stackrel{(\text{sub. } \gamma_d)}{=} 100 \left[ \frac{\gamma_{df} - \gamma_{di}}{\gamma_{di}} \right] \\
 &= 100 \left[ \frac{\gamma_{df}}{\gamma_{di}} - 1 \right]
 \end{aligned}$$

Where:

$V_{SH}$  = Percent volumetric change

$V_i$  = Initial volume

$V_f$  = Final volume

$\gamma_{df}$  = Final dry density

$\gamma_{di}$  = Initial dry density

$W_{fd}$  = Final dry weight of soil

See attachment No. 1 for an example of the calculated values.

*Lorn P. Dunnigan*

LORN P. DUNNIGAN


Head, Soil Mechanics Laboratory

Attachment



## Volumetric Calculations:

$$82W1157 \quad - \quad G_s = 2.69 \quad ; \quad W_{fd} = 3.70 \#$$



$$V_i = \frac{1}{30} \text{ ft}^3 = 0.0333 \text{ ft}^3$$

$$\gamma_{di} = \frac{W_{fd}}{V_i} = \frac{3.7}{\frac{1}{30}} = 111.0 \text{ pcf} = 1.779$$

$$V_f = \frac{\pi D^2 h}{4} = \frac{\pi (3.9805)^2 (4.555)}{4 \times 1728} = 0.0328 \text{ ft}^3$$

$$\gamma_{df} = \frac{W_d}{V_f} = \frac{3.70 \#}{0.0328 \text{ ft}^3} = 112.8 \text{ pcf} = 1.808 \text{ g/cc}$$

$$S_L = w_{sat} = \frac{G_s - \gamma_{df}}{G_s \times \gamma_{df}} = \frac{2.69 - 1.808}{2.69 \times 1.808} \times 100 = 18.15 \%$$

$$V_{SH} = \frac{V_i - V_f}{V_f} = \frac{0.0333 - 0.0328}{0.0328} \times 100 = 1.6 \%$$

or

$$V_{SH} = \left( \frac{\gamma_{df}}{\gamma_{di}} - 1 \right) \times 100 = \left( \frac{1.808}{1.779} - 1 \right) \times 100 = 1.6 \%$$

$$L.S. = \left( 1 - \sqrt[3]{\frac{100}{V_{SH} + 100}} \right) \times 100 = \left( 1 - \sqrt[3]{\frac{100}{1.6 + 100}} \right) \times 100 = 53 \%$$





CONSTRUCTION MONITORING TEST RESULTS<sup>1</sup>

Station	Depth <sup>2</sup> (ft)	Corrected <sup>3</sup> Moisture Content (%)	Dry Density <sup>4</sup> (pcf)	Optimum Moisture Content (%)	Maximum Dry Density (pcf)	Percent Compaction	Percent Fines
265+00	6.2	7.4	125.0	8.7	130.7	95.6	19.3
265+00	9.2	8.5	122.7	9.6	128.1	95.8	16.1
265+00	16.2	8.0	121.9	8.7	128.8	94.6	27.4
265+00	18.3	9.6	128.9	11.4	124.8	103.3	18.7
265+00	22.5	8.4	122.8	10.0	129.3	95.0	26.4
280+00	5.5	8.6	123.8	9.6	126.8	97.6	33.8
280+00	12.0	10.1	118.3	10.6	124.7	94.9	30.2
280+00	16.0	9.7	120.5	11.0	124.9	96.5	22.4
280+00	20.5	11.0	120.7	10.7	126.6	95.3	24.0
280+00	27.0	10.2	123.1	10.6	123.5	99.6	29.4

<sup>1</sup>Test results provided by Mr. Nick Karan (Chief, Engineering Division Maricopa County Flood Control District)

<sup>2</sup>Depth below crest of embankment

<sup>3</sup>Moisture content of material passing #4 sieve

<sup>4</sup>Dry density of material passing #4 sieve



Date 6/16/86

Checked By KEN RICKER

Date 6/16/86

Prepared By s.f.


Date 6/16/86

Checked By

Date



STA. 265+00



STA. 280+00



Date 6/16/86

Date

Checked By KEN RICKER


Checked By

Date 6/16/86


Date

Prepared By s.f.

Prepared By



DENNISON SAMPLER



PREPARING DENNISON  
SAMPLE FOR EXTRUSION



JOB NO. 2126J296  
SPOOKHILL DAM

Prepared By \_\_\_\_\_ Date 6/16/86

Checked By KEN RICKER

Date 6/16/86

s.f. \_\_\_\_\_



21253296  
# 2  
Sta. 280+00  
(22.5-29.5')





**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

Flood Control District of Maricopa County  
3335 West Durango Street  
Phoenix, Arizona 85009

October 11, 1984

Attn: Mr. Nick Karan, P.E.

Re: Shrinkage Limit Tests  
Spook Hill Dam

Job No. 2184J017

Shrinkage limit tests were conducted according to ASTM Designation D427-83 which states that the initial water content for the test should be equal or slightly greater than the liquid limit. Using this procedure often results in shrinkage limit values greater than the plastic limit for sandy and silty clays (Holtz and Kovacs).

The soils tested were silty or clayey sands with 20.5% to 35.3% passing the 200 mesh sieve. High shrinkage limit values could be expected for soils that are predominately sands. The grain to grain contact would occur primarily between sand particles and the size of capillaries that produce tension upon drying would be relatively large in diameter. Capillary tension and resulting shrinkage would be low; therefore, little shrinkage would occur and the shrinkage limit would be high.

Shrinkage limit test results are meaningful only for clays and published interpretations may be applied only to clay soils. For clays, Holtz and Gibbs present the following information for arid region soils: A shrinkage limit greater than 12 has little volume change potential. Bowles says that it is not possible to quantify the term "little volume change potential".

References:

Holtz and Kovacs, "An Introduction to Geotechnical Engineering", 1981, Prentice-Hall, pages 178-185

Bowles, "Physical and Geotechnical Properties of Soils", 1979, McGraw-Hill, pages 223-225.

We hope this information assist you in the interpretation of the attached test results. If we may be of further service please don't hesitate to contact us.

Respectfully submitted,  
WESTERN TECHNOLOGIES INC.

*John C. Rosner*  
John C. Rosner, Ph.D., P.E.

nj

Attachments

Copies to: Addressee (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 1 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 265-6.6 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- <span style="float: right;">LL = _____ PI = _____</span>
2½"			Moisture - Density Relations <span style="float: right;">Maximum Dry Density, pcf _____</span> <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ <span style="float: right;">Optimum Moisture, % _____</span>
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- <span style="float: right;">Specific Gravity _____</span>
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- <span style="float: right;">'R' Value _____</span>
½"			
⅜"			Other: Moisture Content, % ASTM D2216 <span style="float: right;">7.4</span>
¼"			
No. 4			Shrinkage Limit, % ASTM D427 <span style="float: right;">12.6</span>
8			
10			
16			
30			
40			
50			
100			
200	35.3		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 2 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 265-9.2      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      7.8
¼"			
No. 4			Shrinkage Limit, % ASTM D427      22.7
8			
10			
16			
30			
40			
50			
100			
200	30.4		
Finer than 200 ASTM D1140-			

Copies to:      Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 3 of 9

Client **Flood Control District**  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date \_\_\_\_\_  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84

Type of Material --      Submitted By WTI      Date 8/29/84

Source of Material Station 265-16.2      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2 1/2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1 1/2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
3/4"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
1/2"			
3/8"			Other: Moisture Content, % ASTM D2216      7.8
1/4"			
No. 4			Shrinkage Limit, % ASTM D427      25.7
8			
10			
16			
30			
40			
50			
100			
200	28.9		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 4 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 265-18.3      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      8.3
¼"			
No. 4			Shrinkage Limit, % ASTM D427      22.7
8			
10			
16			
30			
40			
50			
100			
200	20.5		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 5 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84  
Type of Material -- Submitted By WTI Date 8/29/84  
Source of Material Station 265-22.5 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216 7.1
¼"			
No. 4			Shrinkage Limit, % ASTM D427 25.5
8			
10			
16			
30			
40			
50			
100			
200	21.0		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 6 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 280-5.5      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2 1/2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1 1/2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
3/4"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
1/2"			
3/8"			Other: Moisture Content, % ASTM D2216      5.8
1/4"			
No. 4			Shrinkage Limit, % ASTM D427      21.3
8			
10			
16			
30			
40			
50			
100			
200	20.9		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 7 of 9

Client **Flood Control District**  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 280-12.0 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216 5.4
¼"			
No. 4			Shrinkage Limit, % ASTM D427 18.6
8			
10			
16			
30			
40			
50			
100			
200	21.7		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 8 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 280-16.0      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      8.5
¼"			
No. 4			Shrinkage Limit, % ASTM D427      19.9
8			
10			
16			
30			
40			
50			
100			
200	24.5		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 9 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 280-20.5 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216 9.7
¼"			
No. 4			Shrinkage Limit, % ASTM D427 26.1
8			
10			
16			
30			
40			
50			
100			
200	32.6		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LETTER OF  
TRANSMITTAL**

To Maricopa County Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009

Date 8/1/86

Job No. 2125J296

Lab./Invoice No.

Ref No.

Attn. Mr. Nick Karan, P.E.; Chief Engineering Division

Project/Subject Shrinkage Testing  
Spookhill Flood Retention Structure  
Maricopa County, Arizona

Please be informed that we are:

<input checked="" type="checkbox"/> Enclosing	Engineering Reports
<input type="checkbox"/> Forwarding Separately	Laboratory Reports
<input type="checkbox"/> Per Your Request	Field Reports
<input type="checkbox"/> 3 No. of Copies	Proposals
<input checked="" type="checkbox"/> Other	

More fully described as follows: Shrinkage limits tests data sheets for remolded samples.  
On these sheets a negative volumetric change, % signifies an increase in volume.

For your:

<input checked="" type="checkbox"/> Use	Information
<input type="checkbox"/> Approval	Action
<input type="checkbox"/> Files	Other

Material forwarded by:

<input type="checkbox"/> Our Messenger	Express Mail
<input type="checkbox"/> Your Messenger	Air Priority
<input checked="" type="checkbox"/> First Class Mail	United Parcel Service
<input type="checkbox"/> Priority Mail	Motor Freight
<input type="checkbox"/> Certified Mail	Air Freight
<input type="checkbox"/> Special Delivery	City Delivery
<input type="checkbox"/> Other	

**FLOOD CONTROL DISTRICT  
RECEIVED**

AUG 4 '86

Copies to:

CH ENG	HYDRO
ASST	LMgt
ADMIN	SUSP
C & O	FILE
ENGR	DESTROY
FINANCE	CGT
REMARKS	

By *Frank Costello*  
Frank Costello

SHRINKAGE LIMITS

Sample ID. STA 265+00 (6.6-7.6)

Job No. 2125J296

Placement Density,pcf	125		Undisturbed	_____
Placement Moisture, %	7.4		Remolded	*
Present Density, gm/cc	1.802	Initial Measurements, in.		
Present Moisture, %	7.4	Height	Width	
Soil Sp. Gr., gm/cc	2.666	4.642	3.985	
		4.601	3.971	
Max. Dry Density, gm/cc	1.743	4.612	3.975	
Minimum Volume, cu. ft.	1.1496	4.632	3.989	
Wt. of Solids, lbs.	4.02		3.979	
			3.984	
Initial Volume, cu. ft.	0.0333			
Int. Dry Density, gm/cc	1.802	4.622	3.981	
		Avg.	Avg.	
Final Volume, cu. ft.	0.0342			
Final Dry Density, gm/cc	1.743	Final Measurements, in.		
		Height	Width	
Shrinkage Limit, %	19.88	4.691	4.011	
Volumetric Shrinkage, %	-2.7	4.694	4.009	
Linear Shrinkage, %	_____	4.655	4.010	
		4.653	4.013	
Volumetric Change, %	-2.7		4.021	
Wt. After Drying, Lbs.	3.72		4.016	
		4.673	4.013	
		Avg.	Avg.	

---

SHRINKAGE LIMITS

Sample ID. STA 265+00 (9.2-10.2)

Job No. 2125J296

Placement Density, pcf 122.7  
 Placement Moisture, % 8.5

Undisturbed \_\_\_\_\_  
 Remolded \*

Present Density, gm/cc 1.926  
 Present Moisture, % 8.5  
 Soil Sp. Gr., gm/cc 2.693  
 Max. Dry Density, gm/cc 1.931  
 Minimum Volume, cu. ft. 1.0185  
 Wt. of Solids, lbs. 4.12

Initial Measurements, in.  
 Height Width  
 4.496 3.936  
 4.476 3.935  
 4.500 3.927  
 4.506 3.935  
 3.926  
 3.936

Initial Volume, cu. ft. 0.0316  
 Int. Dry Density, gm/cc 1.926

4.495 3.933  
 Avg. Avg.

Final Volume, cu. ft. 0.0320  
 Final Dry Density, gm/cc 1.931

Final Measurements, in.  
 Height Width  
 4.458 3.977  
 4.459 3.974  
 4.454 3.979  
 4.452 3.978

Shrinkage Limit, % 14.66  
 Volumetric Shrinkage, % -1.4  
 Linear Shrinkage, % \_\_\_\_\_

Volumetric Change, % -1.4  
 Wt. After Drying, Lbs. 3.86

4.456 3.978  
 Avg. Avg.

Station 265+00

SHRINKAGE LIMITS

Job No. 2125-296

Sample ID. 16-2-18.2

Placement Density, pcf	121.9	Undisturbed
Placement Moisture, %	8.0	Remolded *

Present Density, gm/cc	1.938	Initial Measurements, in.	
Present Moisture, %	8.0	Height	Width
Soil Sp. Gr., gm/cc	2.710	4.469	3.983
		4.466	3.982
Max. Dry Density, gm/cc	1.956	4.471	3.977
Minimum Volume, cu. ft.	0.9990	4.466	3.982
Wt. of Solids, lbs.	4.2		3.975
			3.979

Initial Volume, cu. ft.	0.0322		
Int. Dry Density, gm/cc	1.938	4.468	3.980
		Avg.	Avg.

Final Volume, cu. ft.	0.0320	Final Measurements, in.	
Final Dry Density, gm/cc	1.956	Height	Width
Shrinkage Limit, %	14.24	4.412	3.984
Volumetric Shrinkage, %	0.4	4.475	3.982
Linear Shrinkage, %	-----	4.414	3.987
		4.470	3.982
Volumetric Change, %	0.4		3.980
Wt. After Drying, Lbs.	3.91		3.986
		4.443	3.984
		Avg.	Avg.

SHRINKAGE LIMITS

Sample ID. STA 265+00 (18.3-20.3)

Job No. 2125J296

Placement Density,pcf	128.9		Undisturbed	_____
Placement Moisture, %	9.6		Remolded	*
Present Density, gm/cc	1.853	Initial Measurements, in.		
Present Moisture, %	9.6	Height	Width	
Soil Sp.Gr., gm/cc	2.679	4.608	3.977	
		4.607	3.981	
Max. Dry Density, gm/cc	1.859	4.592	3.979	
Minimum Volume, cu. ft.	1.1112	4.584	3.966	
Wt. of Solids, lbs.	4.19		3.975	
			3.989	
Initial Volume, cu. ft.	0.0331			
Int. Dry Density, gm/cc	1.853	4.598	3.978	
		Avg.	Avg.	
Final Volume, cu. ft.	0.0329			
Final Dry Density, gm/cc	1.859	Final Measurements, in.		
		Height	Width	
Shrinkage Limit, %	16.47	4.603	3.962	
Volumetric Shrinkage, %	0.4	4.600	3.967	
Linear Shrinkage, %	_____	4.571	3.976	
		4.602	3.971	
Volumetric Change, %	0.4		3.975	
Wt. After Drying, Lbs.	3.82		3.977	
		4.594	3.971	
		Avg.	Avg.	

---

SHRINKAGE LIMITS

Sample ID. STA 265+00 (20.2-22.2)

Job No. 2125J296

Placement Density, pcf	122.8	Undisturbed	_____
Placement Moisture, %	8.4	Remolded	*
Present Density, gm/cc	1.995	Initial Measurements, in.	
Present Moisture, %	8.4	Height	Width
Soil Sp. Gr., gm/cc	2.716	4.2667	3.957
		4.259	3.960
Max. Dry Density, gm/cc	1.988	4.277	3.965
Minimum Volume, cu. ft.	0.9897	4.273	3.953
Wt. of Solids, lbs.	4.11		3.965
			3.973
Initial Volume, cu. ft.	0.0305		
Int. Dry Density, gm/cc	1.995	4.269	3.962
		Avg.	Avg.
Final Volume, cu. ft.	0.0306		
Final Dry Density, gm/cc	1.988	Final Measurements, in.	
		Height	Width
Shrinkage Limit, %	13.47	4.266	3.975
Volumetric Shrinkage, %	-0.5	4.241	3.969
Linear Shrinkage, %	_____	4.252	3.983
		4.287	3.977
Volumetric Change, %	-0.5		3.974
Wt. After Drying, Lbs.	3.8		3.980
		4.262	3.976
		Avg.	Avg.

---

SHRINKAGE LIMITS

Sample ID. STA 280+00 (5.5-6.5)

Job No. 2125J296

Placement Density,pcf	123.8	Undisturbed	_____
Placement Moisture, %	8.6	Remolded	*
Present Density, gm/cc	1.894	Initial Measurements, in.	
Present Moisture, %	8.5	Height	Width
Soil Sp. Gr., gm/cc	2.695	4.437	3.934
		4.43	3.935
Max. Dry Density, gm/cc	1.898	4.426	3.927
Minimum Volume, cu. ft.	1.0452	4.426	3.925
Wt. of Solids, lbs.	3.99		3.927
			3.937
Initial Volume, cu. ft.	0.0311		
Int. Dry Density, gm/cc	1.894	4.430	3.931
		Avg.	Avg.
Final Volume, cu. ft.	0.0321		
Final Dry Density, gm/cc	1.898	Final Measurements, in.	
		Height	Width
Shrinkage Limit, %	15.58	4.442	3.981
Volumetric Shrinkage, %	-3.0	4.471	3.982
Linear Shrinkage, %	_____	4.443	3.981
		4.447	3.981
Volumetric Change, %	-3.0		3.990
Wt. After Drying, Lbs.	3.8		3.979
		4.451	3.982
		Avg.	Avg.

---

SHRINKAGE LIMITS

Sample ID. STA 280+00 (12.0-13.0)

Job No. 2125J 296

Placement Density,pcf	118.3		Undisturbed	_____
Placement Moisture, %	10.1		Remolded	*
Present Density, gm/cc	2.007	Initial Measurements, in.		
Present Moisture, %	10.1	Height	Width	
Soil Sp. Gr., gm/cc	2.643	4.108	3.932	
		4.111	3.94	
Max. Dry Density, gm/cc	1.997	4.206	3.936	
Minimum Volume, cu. ft.	0.9496	4.217	3.926	
Wt. of Solids, lbs.	4.03		3.929	
			3.926	
Initial Volume, cu. ft.	0.0292			
Int. Dry Density, gm/cc	2.007	4.161	3.932	
		Avg.	Avg.	
Final Volume, cu. ft.	0.0294			
Final Dry Density, gm/cc	1.997	Final Measurements, in.		
		Height	Width	
Shrinkage Limit, %	12.25	4.154	3.926	
Volumetric Shrinkage, %	-0.5	4.146	3.924	
Linear Shrinkage, %	_____	4.231	3.928	
		4.233	3.921	
Volumetric Change, %	-0.5		3.931	
Wt. After Drying, Lbs.	3.66		3.933	
		4.191	3.927	
		Avg.	Avg.	

---

SHRINKAGE LIMITS

Sample ID. STA 280+00 (16.0-18.0)

Job No. 2125J 296

Placement Density,pcf	120.5	Undisturbed	_____
Placement Moisture, %	9.7	Remolded	*
Present Density, gm/cc	1.921	Initial Measurements, in.	
Present Moisture, %	9.7	Height	Width
Soil Sp. Gr., gm/cc	2.717	4.582	3.985
		4.618	3.982
Max. Dry Density, gm/cc	1.924	4.622	3.973
Minimum Volume, cu. ft.	1.0036	4.600	3.982
Wt. of Solids, lbs.	4.36		3.972
			3.987
Initial Volume, cu. ft.	0.0332		
Int. Dry Density, gm/cc	1.921	4.606	3.980
		Avg.	Avg.
Final Volume, cu. ft.	0.0332		
Final Dry Density, gm/cc	1.924	Final Measurements, in.	
		Height	Width
Shrinkage Limit, %	15.17	4.612	3.981
Volumetric Shrinkage, %	-0.2	4.619	3.981
Linear Shrinkage, %	_____	4.607	3.980
		4.617	3.983
Volumetric Change, %	-0.2		3.980
Wt. After Drying, Lbs.	3.99		3.980
		4.614	3.981
		Avg.	Avg.

SHRINKAGE LIMITS

Sample ID. STA 280+00 (18.0-20.0)

Job No. 2125J296

Placement Density,pcf	120.7	Undisturbed	_____
Placement Moisture, %	11.0	Remolded	*
Present Density, gm/cc	1.911	Initial Measurements, in.	
Present Moisture, %	11.1	Height	Width
Soil Sp. Gr., gm/cc	2.695	4.545	3.979
		4.542	3.979
Max. Dry Density, gm/cc	1.924	4.547	3.978
Minimum Volume, cu. ft.	1.0051	4.500	3.972
Wt. of Solids, lbs.	4.32		3.980
			3.982
Initial Volume, cu. ft.	0.0326		
Int. Dry Density, gm/cc	1.911	4.534	3.978
		Avg.	Avg.
Final Volume, cu. ft.	0.0327		
Final Dry Density, gm/cc	1.924	Final Measurements, in.	
		Height	Width
Shrinkage Limit, %	14.86	4.571	3.980
Volumetric Shrinkage, %	-0.4	4.572	3.982
Linear Shrinkage, %	_____	4.548	3.978
		4.501	3.978
Volumetric Change, %	-0.4		3.981
Wt. After Drying, Lbs.	3.93		3.975
		4.548	3.979
		Avg.	Avg.

---

SHRINKAGE LIMITS

Sample ID. STA 280+00 (20.5-22.5)

Job No. 2125J296

Placement Density,pcf 120.7  
 Placement Moisture,% 11.0

Undisturbed \_\_\_\_\_  
 Remolded \*

Present Density,gm/cc 1.980  
 Present Moisture,% 11.0  
 Soil Sp.Gr.,gm/cc 2.690  
 Max. Dry Density,gm/cc 1.964  
 Minimum Volume,cu.ft. 0.9850  
 Wt. of Solids,lbs. 4.16

Initial Measurements,in.  
 Height Width  
 4.213 3.976  
 4.282 3.976  
 4.226 3.972  
 4.214 3.966  
 3.965  
 3.969

Initial Volume,cu.ft. 0.0303  
 Int. Dry Density,gm/cc 1.980

4.234 3.971  
 Avg. Avg.

Final Volume,cu.ft. 0.0305  
 Final Dry Density,gm/cc 1.964

Final Measurements,in.  
 Height Width  
 4.206 3.974  
 4.23 3.976  
 4.25 3.976  
 4.289 3.98

Shrinkage Limit,% 13.75  
 Volumetric Shrinkage,% -0.6  
 Linear Shrinkage,% \_\_\_\_\_

Volumetric Change,% -0.6  
 Wt. After Drying,Lbs. 3.74

4.244 3.978  
 Avg. Avg.



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

Maricopa County Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009

June 27, 1985

*Superseded*

Attn: Mr. Nick Karan, P.E.  
Chief, Engineering Division

Re: Geotechnical Services  
Spookhill FRS

Ref. No. 2125A128  
Revision No. 1

We are pleased to present this proposal to perform some geotechnical sampling and testing services for the existing Spookhill Flood Retention Structure. This proposal presents a recommended plan of operations and fees for the services described.

Based on our discussions, it is our understanding that undisturbed and disturbed samples are required for shrinkage testing from various elevations at two locations on the existing embankment. The following sample locations are required:

<u>Station</u>	<u>Depth (ft)</u>
265+00	6.6
	9.2
	16.2
	18.3
	22.2
280+00	5.5
	12.0
	16.0
	20.5
	27.0

FLOOD CONTROL DISTRICT

Drilling and sampling are to be performed from the crest of the embankment, and the depths shown are below crest elevation.

JUL 02 '85

CH ENG	HYDRO
ASST	LMgt
ADMIN	SUSP
C & O	FILE
ENGR	DESTROY
FINANCE	
REMARKS	

PLAN OF OPERATIONS

The following procedures would be utilized in an attempt to obtain relatively undisturbed samples of existing embankment material at the locations and depths specified:

1. The four relatively shallow samples (6.6, 9.2 and 5.5, 12.0) would be taken in backhoe test pits by block sampling using SCS recommended methods. Excavation and subsequent backfilling of the test pits would be performed by Maricopa County personnel.
2. The deeper samples at each location would be taken with a drill rig using one of the following methods (listed in order of attempt):
  - a. Shelby Tube
  - b. Dennison Sampler (7-inch diameter)
  - c. Soils Core Barrel
3. Disturbed samples would be taken at each location corresponding to an undisturbed sample.

It should be noted that due to the reported granular nature of the embankment fill material, we may be unable to obtain a representative undisturbed sample using any of these methods.

Shrinkage testing (shrinkage limit, volumetric shrinkage, lineal shrinkage) would be performed on both the disturbed and undisturbed samples from each location in accordance with the SCS procedures included in your transmittal.



FEE SCHEDULE

The following fees would apply to the services previously described. The initial attempt would include an experienced field engineer to perform block sampling on the four shallow samples. The fee for this phase would be \$250.00 per block sample attempt. It is understood that the backhoe and operator would be provided by others.

If we are unable to obtain shallow block samples due to the granular nature of the fill material, it is highly unlikely that suitable deeper undisturbed samples could be obtained by drilling methods. At this point we would recommend that the exploration program be terminated.

If we are successful at obtaining shallow block samples, the next phase of the exploration would include the following:

Mobilization/Demobilization	\$ 650.00
Drilling (est. 3 days)	<u>\$3730.00*</u>
Subtotal	\$4380.00

During the drilling operation we would attempt to obtain undisturbed samples at the depths requested utilizing one of the following methods (listed in order of attempt):

Shelby Tube (per sample attempt)	\$ 35.00
Dennison Sampler (per sample attempt)	\$ 165.00
Soil Core Barrel (per sample attempt)	\$ 120.00

\*Based on \$40.40 per foot

- includes all footage
- includes field engineer
- does not include sample attempts



Maricopa County Flood Control District  
Ref. No. 2125A128


Laboratory testing would be performed in accordance with the SCS procedures included in your transmittal at the following rates:

Disturbed Sample (per each)	\$ 147.50
Undisturbed Sample (per each)	\$ 177.50

Based on these fees, the anticipated work would be performed for a total fee not to exceed \$9750.00. Any additional work which might be indicated by the discovery of unanticipated conditions in the field will be performed, upon your authorization, in accordance with our current fee schedule. This proposal is intended to remain valid until July 31, 1985, at which time it would require review and possible revision. This revision should replace our original proposal dated June 19, 1985.

Respectfully submitted,

WESTERN TECHNOLOGIES INC.  
Geotechnical Services




Craig P. Wiedeman, P.E.

jh

Copies to: Addressee (2)





# FLOOD CONTROL DISTRICT

of

*Maricopa County*

3335 West Durango Street • Phoenix, Arizona 85009

Telephone (602) 262-1501

D. E. Sagramoso, P.E., Chief Engineer and General Manager

BOARD of DIRECTORS

Tom Freestone, Chairman

George L. Campbell

Carole Carpenter

Fred Koory, Jr.

Ed Pastor

May 22, 1985

Mr. John C. Rosner, Ph.D., P.E.  
Western Technologies, Inc.  
3737 East Broadway Road  
Phoenix, AZ 85036

Dear John:

Enclosed please find a copy of the information from SCS outlining procedures for additional testing to be performed at the Spook Hill FRS.

After you have a chance to review this information, please give me a call so that we may further discuss this matter.

Sincerely,

Nick Karan, P.E.  
Chief, Engineering Division

Enclosure

NPK/jet

FILE:

INFO: CGF  
SLS  
DES



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

201 E. Indianola Ave.  
Suite 200  
Phoenix, Arizona 85012

March 12, 1985

Dan Sagramoso  
Chief Engineer and General Manager  
Flood Control District of Maricopa County  
3335 West Virginia Street  
Phoenix, Arizona 85009

Dear Dan:

We have received the attached laboratory procedure for determining shrinkage, limits volumetric shrinkage and lineal shrinkage from our Portland Office. This is a follow-up to your report on abandonment of the Spookhill FRS Irrigation System. We had agreed to obtain procedure whereby undisturbed test data could be used for comparative shrinkage analysis.

After you review please contact this office for a meeting to discuss the subject further.

Sincerely,

Verne M. Bathurst  
State Conservationist

Enclosure

FLOOD CONTROL DISTRICT  
RECEIVED

MAR 14 '85

	CH ENG	HYDRO
	ASST	LMgt
	ADMIN	SUSP
	C & O	FILE
1	ENGR	DESTROY
	FINANCE	2 CGF
REMARKS		



The Soil Conservation Service  
is an agency of the  
Department of Agriculture

SCS-AS-1A  
10-79



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

West National Technical Center  
511 N. W. Broadway, Room 547  
Portland, Oregon 97209-3489

82  
#6.P.

Subject: ENG - Soil Mechanics - Shrinkage Limits

Date: February 26, 1985

To: Ralph Arrington, State Conservation Engineer,  
SCS, Phoenix, Arizona

File Code:

Attached is a letter from the Lincoln Laboratory indicating the procedure for making shrinkage limits on compacted soils. The letter does not give the instructions I was hoping for but should be sufficient with the following additions:

1. Prepare a compacted specimen using soil from the same area of the fill an undisturbed sample was obtained. Prepare the sample in accordance with the ASTM Standard test procedure used for design of the fill. The dry density and moisture content shall be in accordance with the design specifications for the fill.
2. Extrude the specimen and dry according to the instructions in the attached letter. Determine  $G_s$  and moisture content of the soil.
3. Determine the volume of the mold in accordance with section 3.1.3 ASTM D698.
4. After the specimen has been dried, determine the average diameter, height and volume. The average of the diameter, height and volume shall be calculated from at least six diameter and three height measurements made to the nearest 0.001 in. (0.02 mm).
5. Make shrinkage calculations in accordance with attached letter.
6. Obtain an undisturbed sample of the fill. Determine  $G_s$  and moisture content for the sample.
7. Determine the average diameter, height and volume using measurement procedures similar to item 4.
8. Dry the undisturbed sample according to the attached letter.
9. Determine the average diameter, height and volume using measurement procedures similar to item 4.



10. Make shrinkage calculations in accordance with attached letter.
11. Plot the moisture contents and shrinkage limits percent vs. the dry density values for the remolded and undisturbed samples.
12. Calculate the theoretical minimum volume possible for the soil by using the following equation:

$$V_{\min} = \frac{(W_s)(SL)}{\gamma_w} + \frac{W_s}{G_s \gamma_w}$$

where  $W_s$  = W+ of solids

SL = Shrinkage limit at Placement density in decimal.

13. Calculate volume associated with the in place density and assume one for the placement density volume.
14. Evaluate the volumetric shrinkage to determine the amount completed since construction and what is left yet to reach a minimum volume.
15. Following is an example set of calculations and comparison:

a. Placement density = 1.83 gm/cc

b. Present in place density = 1.87 gm/cc

c.  $G_s = 2.949$  and SL = 19%

d.

$$V_{\min} = \frac{(1.83)(.19)}{1} + \frac{1.83}{(2.949)} = 0.9683$$

e.

$$\gamma_{d_{\max}} = \frac{W_s}{V_{\min.}} = \frac{1.83}{.9683} = 1.89 \text{ gm/cc}$$

f.

$$\gamma = \frac{W_s}{V} \quad V = \frac{W_s}{\gamma} = \frac{1.83}{1.87} = 0.9786 \text{ ft}^3$$

g.


Condition	$\gamma_d$	$W_s$	Vol.	* Min. Vol. Sh.
Constructed	1.83	1.83	1.000	
Present	1.87	1.83	0.9786	
Min. Vol.	1.89	1.83	0.9683	7.2%

$$* \frac{1.0 - .9683}{1.0 - .9786} = \frac{x}{22-12} \quad x = 14.8 \quad A = 22-14.8 = 7.2$$

h.

$$\% C = \frac{1.0 - .9786}{1.0 - .9683} \times 100 = 67.5\% = \text{Amount of Vol. Shrinkage that has occurred to date.}$$

i. Plot of data and resulting calculations.



Ralph Arrington  
February 26, 1985

4

If I can be of further assistance please let me know.

*C.E. Deal for*

CLIFTON E. DEAL  
Soil Mechanics Engineer

Attachment

cc:

Susanne Leckband, Design Engineer,  
SCS, Phoenix, Arizona

Verne Bathurst, State Conservationist,  
SCS, Phoenix, Arizona

Jack C. Stevenson, Head, Engineering Staff, WNTC



Subject: ENG - Soil Mechanics - Shrinkage Limits,  
Volumetric Shrinkage and Lineal Shrinkage

Date: February 12, 1985

To: Clifton E. Deal  
Soil Mechanics Engineer  
WNTC, SCS, Portland, OR

File Code: 210-22

Shrinkage limits, volumetric shrinkage and lineal shrinkage on puddled soils using the procedure of ASTM D427 are highly dependent on how much moisture the soil contains at the start and have little direct application for determining the shrinkage characteristics of a compacted soil. Better predictions can be made for compacted soil by compacting the soil at the proposed placement moisture and making direct volume and density measurements before and after drying to a constant volume.

The soil must be dried slowly and carefully to avoid drying cracks from forming that will affect the actual volume of the dried specimen. A moist room can be used for the initial drying to prevent cracking. Usually, several days are required in the moist room. An alternate method of drying is to place the newly compacted specimens in sealed plastic bags and open the plastic bags for a few minutes at a time several times a day until the bags can be left open to dry at room temperature without cracking. Final drying in a standard oven should continue until no further moisture loss is obtained.

The following relationships are used to calculate the shrinkage properties.

$$V_{SH} = \frac{V_i - V_f}{V_f} \times 100$$

$$L.S. = \left( 1 - \sqrt[3]{\frac{100}{V_{SH} + 100}} \right) \times 100$$

$$S.L. = w_{sat} = \frac{G_S - \gamma d_f}{G_S \times \gamma d_f} \times 100$$

Where:

$V_{SH}$  = Volumetric shrinkage

$V_i$  = Initial volume

$V_f$  = Final volume

L.S. = Lineal shrinkage

S.L. = Shrinkage limit

$\gamma d_f$  = Final dry density

$G_S$  = Specific gravity of soil



For soil specimens with shapes that are not conducive to accurate measurements with a ruler, the relationships can be determined using densities determined by displacement methods such as coating the soil with wax and determining volume by the difference of the weights of the soil in air and in water.

The volumetric shrinkage relationship and the density relationships are derived as follows:

Volume shrinkage is defined as the change in volume divided by the final volume.

$$\begin{aligned}
 V_{SH} &= \frac{V_i - V_f}{V_f} \times 100 \quad (\div V_i) \quad \left[ \frac{V_i - V_f}{\frac{V_i}{V_f}} \right] \quad \text{Regroup} \quad \left[ \frac{V_i - V_f}{\frac{1}{V_i}} \right] \quad \text{Rearrange} \\
 &= 100 \left[ \frac{1}{V_f} - \frac{1}{V_i} \right] \quad (\times W_{fd}) \quad \left[ \frac{\frac{W_{fd}}{V_f} - \frac{W_{fd}}{V_i}}{\frac{W_{fd}}{V_i}} \right] \quad \text{(sub. } \gamma_d) \quad \left[ \frac{\gamma_{df} - \gamma_{di}}{\gamma_{di}} \right] \\
 &= 100 \left[ \frac{\gamma_{df}}{\gamma_{di}} - 1 \right]
 \end{aligned}$$

Where:

$V_{SH}$  = Percent volumetric change

$V_i$  = Initial volume

$V_f$  = Final volume

$\gamma_{df}$  = Final dry density

$\gamma_{di}$  = Initial dry density

$W_{fd}$  = Final dry weight of soil

See attachment No. 1 for an example of the calculated values.


*Lorn P. Dunningan*

LORN P. DUNNIGAN  
Head, Soil Mechanics Laboratory

Attachment

## Volumetric Calculations

$$82W1157 = G_s = 2.69 ; W_{fd} = 3.70 \#$$



$$V_i = 1/30 \text{ ft}^3 = 0.0333 \text{ ft}^3$$

$$\delta_{di} = \frac{W_{fd}}{V_i} = \frac{3.7}{1/30} = 111.0 \text{ pcf} = 1.779$$

$$V_f = \frac{\pi D^2 h}{4} = \frac{\pi (3.9805)^2 (4.555)}{4 \times 1728} = 0.0328 \text{ ft}^3$$

$$\delta_{df} = \frac{W_{fd}}{V_f} = \frac{3.70 \#}{0.0328 \text{ ft}^3} = 112.8 \text{ pcf} = 1.808 \text{ g/cc}$$

$$S.L. = w_{sat} = \frac{G_s - \delta_{df}}{G_s \times \delta_{df}} = \frac{2.69 - 1.808}{2.69 \times 1.808} \times 100 = 18.15 \%$$

$$V_{SH} = \frac{V_i - V_f}{V_f} = \frac{0.0333 - 0.0328}{0.0328} \times 100 = 1.6 \%$$

or

$$V_{SH} = \left( \frac{\delta_{df}}{\delta_{di}} - 1 \right) \times 100 = \left( \frac{1.808}{1.779} - 1 \right) \times 100 = 1.6 \%$$

$$L.S. = \left( 1 - \sqrt[3]{\frac{100}{V_{SH} + 100}} \right) \times 100 = \left( 1 - \sqrt[3]{\frac{100}{1.6 + 100}} \right) \times 100 = 53 \%$$



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

Suite 200, 201 East Indianola  
Phoenix, Arizona 85012

January 3, 1985

Mr. Dan Sagramoso, P.E.  
Chief Engineer and General Manager  
Flood Control District of Maricopa Co.  
3335 West Durango Street  
Phoenix, Arizona 85009

Dear Dan:

We have reviewed your "Report on Abandonment of Spook Hill FRS Irrigation System." We desire to address the one issue regarding the shrinkage test data presented.

The shrinkage test conducted under the procedure of ASTM D427 is made on saturated, disturbed samples. The embankment fill materials are placed at a moisture content below saturation. In-place stresses are imparted to the fill that may change the shrinkage limit values.

Laboratory tests have been made on undisturbed samples taken from existing dams with the relationship as shown on the attached shrinkage limit diagram.

Without comparative shrinkage analysis on undisturbed samples from the existing structure, it is not possible to determine whether cracking due to desiccation has reached a steady state.

Undisturbed tests were conducted on the Rittenhouse FRS by the FCD and the results showed additional shrinkage was expected for that structure.

My staff will discuss this topic at the next coordination meeting.

Sincerely,

*Don R. Phillips*

Acting For

Verne M. Bathurst  
State Conservationist

Attachment

FLOOD CONTROL DISTRICT  
RECEIVED

JAN 04 '85

5	CH ENG	HYDRO
4	ASST	LMet
	ADMIN	SUSP
1	<i>MP</i>	FILE
2	ENGR	DESTROY
	FINANCE	<del>DESTROY</del>
REMARKS		6 c + 0




The Soil Conservation Service  
is an agency of the  
United States Department of Agriculture



# Shrinkage Limit Diagram

CED

11/84





FLOOD CONTROL DISTRICT of Maricopa County

Interoffice Memorandum

CMT. NO.	SUBJECT: Spook Hill FRS Sprinklers	<input checked="" type="checkbox"/> FILE <input type="checkbox"/> DESTROY
----------	------------------------------------	--


TO: CWM  
via  
RCP

FROM: NPK

DATE: 10-31-84

Please add the following to your Report on Spook Hill FRS:


At the request of our O & M Division, Western Technologies, Inc. in May 1983 performed in situ moisture tests on 20 samples obtained at sta ~~286+90~~ 280+00 and 22 samples at sta 286+90. A tabulation of the in situ moisture contents is ~~hereto~~ attached. In all the cases the in situ moisture contents are considerably lower than those at the time of construction. Additional tests were performed by Western Technologies, ~~at~~ in September 1984 at the request of our Engineering Division. These tests ~~investigated~~ included



FLOOD CONTROL DISTRICT of Maricopa County

Interoffice Memorandum

CMT. NO.	SUBJECT:	<input type="checkbox"/> FILE _____ <input type="checkbox"/> DESTROY _____	
	TO:	FROM:	DATE:
<p><del>The</del> in situ moisture content, Shrinkage Limit and percent passing the #200 sieve.</p> <p><del>Five</del> such tests were performed on samples from Sta 265+00 and four on samples from Sta 280+00</p> <p><del>In all of the tests</del> samples the</p> <p>The percent passing the #200 sieve <del>was</del> ranged between 35.3% and 20.5% indicating coarse grained materials.</p> <p><del>In all of the samples</del> tested, the in situ moisture content was lower than the Shrinkage Limit. Copies of the lab test results are attached.</p> <p>In coarse grained soils the capillary forces causing surface tension are low thereby resulting in low amounts of shrinkage. <del>Furthermore the fact that the present in situ moisture</del></p>			



FLOOD CONTROL DISTRICT of Maricopa County

Interoffice Memorandum

CMT. NO.	SUBJECT:	<input type="checkbox"/> FILE _____ <input type="checkbox"/> DESTROY _____	
	TO:	FROM: <sup>is lost</sup> As moisture <del>evaporates</del> , shrinkage occurs, with the resulting <sup>dessication</sup> cracking, until the moisture content reaches that of the Shrinkage Limit. Further <del>evaporation</del> loss of moisture below the Shrinkage Limit will not result in additional shrinkage or <del>cracking</del> . The fact that the moisture content in all the samples taken is lower than the Shrinkage Limit indicates that no further shrinkage or dessication cracking should be expected. Therefore attempts to prevent further moisture loss by <del>overlapping the</del> continuing to keep the surface of the structure moist are not, <sup>in our opinion,</sup> justified. nick	DATE:

Station 286+90 "A"  
NONIRRIGATED \*

Station 280+00 "B"  
IRRIGATED \*\*

DEPTH IN FT	MOISTURE CONTENT %
1.0	3.4
2.5	3.7
5.0	4.2
7.5	4.9
10.0	5.8
12.5	3.0
15.0	1.2

DEPTH IN FT	MOISTURE CONTENT %
2.5-3.5	5.7
5.0-6.0	7.6
7.5-8.5	3.6
10.0-11.0	7.5
12.5-13.5	9.9
15.0-16.0	7.7
17.5-18.5	10.0
20.0-21.0	8.8

side slope of dam

DEPTH IN FT	MOISTURE CONTENT %
1.0	1.9
2.5	2.6
5.0	4.1
7.5	4.0
10.0	3.5
12.5	3.6

DEPTH IN FT	MOISTURE CONTENT %
0.0-1.5	5.5
5.0-6.0	9.6
7.5-8.5	8.9
10.0-11.0	7.3
12.5-13.5	8.9
15.0-16.0	7.0
17.5-18.5	8.6
20.0-21.0	7.6

toe of dam

DEPTH IN FT	MOISTURE CONTENT %
1.0	5.3
2.5	4.3
5.0	3.1
7.5	5.4
10.0	5.7
12.5	3.8
15.0	3.9
17.5	4.2
20.0	5.7

DEPTH IN FT	MOISTURE CONTENT %
2.5-4.0	6.4
5.0-6.0	8.3
7.5-8.5	8.2
10.0-11.0	8.9

\* Core boring and moisture determinations by Maricopa County Highway Soils Lab using an Auger drill method.

\*\* Core boring and moisture determinations by Western Technologies using methods similar to the above (as observed by FCD personnel).


#1

#2

#3

US

DS





**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LETTER OF  
TRANSMITTAL**

To AZ Flood Control Dist Date 9-18-84  
3335 W. Durango St.  
Phoe AZ 85009 Job No. 2184J017  
 Lab./Invoice No. \_\_\_\_\_  
 Ref. No. \_\_\_\_\_

Attn. MR. Nick Karran

Project/Subject Spook Hill DAM Laboratory Test results

Please be informed that we are:

- Enclosing
- Forwarding Separately
- Per Your Request
- No. of Copies
- Other \_\_\_\_\_
- Engineering Reports
- Laboratory Reports
- Field Reports
- Proposals

More fully described as follows: Nick, I'm enclosing The results on all The  
Samples except Sample # 280-27.0 Feet. The Lab was  
UNable To run Tests on Sample provided so we will have  
To go and get another one. I will coordinate w/ Bob Paet.

For your:

- Use
- Approval
- Files
- Information
- Action
- Other \_\_\_\_\_

Material forwarded by:

- Our Messenger
- Your Messenger
- First Class Mail
- Priority Mail
- Certified Mail
- Special Delivery
- Other \_\_\_\_\_
- Express Mail
- Air Priority
- United Parcel Service
- Motor Freight
- Air Freight
- City Delivery

**FLOOD CONTROL DISTRICT  
RECEIVED**

SEP 19 '84

Copies to:

CH ENG	HYDRO
ASST	LMgt
ADMIN	SUSP
C & D	FILE
ENGR	DESTROY
FINANCE	
REMARKS	

By Gabriel R. Escamilla  
Kelly Black

**PHYSICAL PROPERTIES OF SOILS**

Page 5 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84

Type of Material --      Submitted By WTI      Date 8/29/84

Source of Material Station 265-22.5      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
¼"			Other: Moisture Content, % ASTM D2216      7.1
No. 4			
8			Shrinkage Limit, ml ASTM D427      25.5
10			
16			
30			
40			
50			
100			
200	21.0		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 4 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 265-18.3      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      8.3
¼"			
No. 4			Shrinkage Limit, ml ASTM D427      22.7
8			
10			
16			
30			
40			
50			
100			
200	20.5		
Finer than 200 ASTM D1140-			

Copies to:      Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 3 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date \_\_\_\_\_  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 265-16.2      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      7.8
¼"			
No. 4			Shrinkage Limit, ml ASTM D427      25.7
8			
10			
16			
30			
40			
50			
100			
200	28.9		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 2 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam  
 Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 265-9.2      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      7.8
¼"			
No. 4			Shrinkage Limit, ml ASTM D427      22.7
8			
10			
16			
30			
40			
50			
100			
200	30.4		
Finer than 200 ASTM D1140-			

Copies to:      Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 1 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 265-6.6      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2 1/2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1 1/2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
3/4"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
1/2"			
3/8"			Other: Moisture Content, % ASTM D2216 7.4
1/4"			
No. 4			Shrinkage Limit ml ASTM D427 12.6
8			
10			
16			
30			
40			
50			
100			
200	35.3		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

LABORATORY REPORT

**PHYSICAL PROPERTIES OF SOILS**

Page 9 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 280-20.5      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      9.7
¼"			
No. 4			Shrinkage Limit, ml ASTM D427      26.1
8			
10			
16			
30			
40			
50			
100			
200	32.6		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 8 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 280-16.0      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216 8.5
¼"			
No. 4			Shrinkage Limit, ml ASTM D427 19.9
8			
10			
16			
30			
40			
50			
100			
200	24.5		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

**PHYSICAL PROPERTIES OF SOILS**

Page 7 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 280-12.0 Authorized By FCD/Karren Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216 5.4
¼"			
No. 4			Shrinkage Limit, ml ASTM D427 18.6
8			
10			
16			
30			
40			
50			
100			
200	21.7		
Finer than 200 ASTM D1140-			

Copies to: Client (3)

LABORATORY REPORT

**PHYSICAL PROPERTIES OF SOILS**

Page 6 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karren

Job No. 2184J017  
 Lab/Invoice No. 2184W017  
 Date 9/11/84  
 Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
 Type of Material --      Submitted By WTI      Date 8/29/84  
 Source of Material Station 280-5.5      Authorized By FCD/Karren      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      5.8
¼"			
No. 4			Shrinkage Limit, ml ASTM D427      21.3
8			
10			
16			
30			
40			
50			
100			
200	20.9		
Finer than 200 ASTM D1140-			

Copies to:      Client (3)



**FLOOD CONTROL DISTRICT**  
of  
**Maricopa County**

3335 West Durango Street • Phoenix, Arizona 85009  
Telephone (602) 262-1501

D. E. Sagramoso, P.E., Chief Engineer and General Manager

BOARD of DIRECTORS  
Fred Koory, Jr., Chairman  
Hawley Atkinson  
George L. Campbell  
Tom Freestone  
Ed Pastor

**AUG 21 1984**

Mr. Gabriel R. Escamillo, Jr.  
Manager, Geotechnical Exploration  
Western Technologies Inc.  
3737 East Broadway Road  
Phoenix, Arizona 85036

Re: Soils Investigation at Spook Hill Dam

Dear Mr. Escamillo:

You are hereby authorized to proceed with the soil sampling and laboratory testing for this project in accordance with your proposal dated July 26, 1984 and your subsequent discussions with Nick Karan of my staff.

Soil samples are to be taken at the following locations and depths below the top of dam:

Station 265 + 00

6.6 Feet  
9.2 Feet  
16.2 Feet  
18.3 Feet  
22.5 Feet

Station 280 + 00

5.5 Feet  
12.0 Feet  
16.0 Feet  
20.5 Feet  
27.0 Feet

The depths given above correspond to the top of the sample. The maximum height of the sample shall be eight (8) inches.

The following tests are to be conducted on all the samples obtained:

1. In situ moisture content.
2. Shrinkage Limit.
3. Percent finer than the #200 sieve.

It is requested that a twenty-four hour notice be given to Bob Payette of my staff so that a representative of the Flood Control District be present at the job site in order to unlock gates, point out the two locations where drilling is to be done and verify the depths before the sampling operations are conducted.

We request that the sampling operations be conducted on a day other than Friday.

Page Two

Letter: Soils Investigation at Spook Hill Dam

It is our understanding that the sampling and testing operations will be described in a letter that will accompany the lab results.

It is further understood that the total cost for this project will not exceed the sum of \$1,800.

We are returning herewith a copy of your July 26, 1984 proposal with the General Conditions page properly signed for your files.

Sincerely,

D. E. Sagramoso, P. E.

Enclosure

~~MPK~~  
MPK/ho

COORD:

(SLS)  
8/20

INFO: RCP

CGF

RWS

MP  
3/17  
3/17

File: Coord: M.F.C.



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

Room 3008 Federal Building  
230 North First Avenue  
Phoenix, Arizona 85025

**FLOOD CONTROL DISTRICT  
RECEIVED**

JUL 05 '84

Subject: ENG-Meeting on the need for Continue Irrigation  
on Spookhill FRS for Vegetation & Cracking

Date: June 28, 1984

	CH ENG	HYDRO
	ASST	LMgt
	ADMIN	SUSP
1	C & C	FILE
3	ENGR	DESTROY
	FINANCE	DESTROY
REMARKS		

File Code: 210

To Files

The meeting was called to order at 2:00 p.m. Tuesday June 25, 1984 by Bob Payette in the Flood Control Districts' Conference Room. The participants were as follows:

Ralph Arrington	SCS
Bill Payne	SCS
Stan Smith	FCD
Nick Karan	FCD
Catesby Moore	FCD
Bob Payette	FCD
Dan Lawrence	ADWR

Copies of the vegetation report and the construction records for moisture contents were distributed and discussed.

The report indicates the enhancement of vegetation by irrigation is no longer needed. No shrinkage limits were found in the construction records but it is concluded that the embankment shrinkage limit has been exceeded since the present embankment moisture is approximately 3-4% below the constructed moisture in the irrigated reaches and approximately 6-7% below the constructed moisture in the non-irrigated reach.

Bill Payne placed the tentative results of the subsidence survey on the blackboard. The survey showed the approximate settlement of the top of dam monuments to be 0.03 feet between station 110+00 and station 210+00. As soon as the subsidence survey is checked, copies will be sent to FCD and ADWR. The conclusion made is that since subsidence has not occurred it should not be a future problem on Spookhill. Therefore it is likely not to be a cause of cracking if cracking occurs.

The results of the discussions reduced to three positions which are:

ADWR-They have no objection to stopping the irrigation at this time, however, in the future the damage must be assessed for the need to repair.



June 28, 1984

Meeting on the need to Continue Irrigation on Spookhill FRS

To the Files

FCD-They desire to stop the irrigation since it is not needed for the vegetation and will reduce the large operation and maintenance expenses they are incurring.

SCS-Although continuing the irrigation is not a guarantee against embankment cracking, some benefits are decernible, and if the irrigation is stopped cracking must be expected. If repairs are needed, sponsors must share in the cost liability.

The FCD will prepare a report of findings and conclusions from the present data and send copies to ADWR and SCS. A meeting will be scheduled after the FCD report has been received and reviewed.



Ralph M. Arrington  
State Conservation Engineer

cc: FCD ✓  
ADWR  
Joe Knisley  
Steve Revie  
Jack Stevenson



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

Room 3008 - Federal Building  
230 North First Avenue  
Phoenix, Arizona 85025

Subject: PROJ DEV MAINT - Watershed Protection  
Evaluation of Vegetation on  
Spook Hill Structure - 4/12/84

Date: May 23, 1984

To: ~~Robert B. Crawford  
State Resource Conservationist  
Soil Conservation Service  
Phoenix, Arizona~~

File Code: 390-11-21

Ralph Arrington, State Engineer, requested an evaluation on vegetative measures for determining what the impact of discontinuation of irrigation on the structure would have on present vegetative cover. Members participating in the evaluation were:

Catesby Moore, Landscape Architect, Maricopa Flood Control District  
Carl Pachek, Agronomist, Soil Conservation Service, Phoenix  
Jake Garrison, Plant Materials Specialist, SCS, Phoenix  
Steve Revie, District Conservationist, SCS, Chandler

Starting on the southeast end, the vegetation is good to fair. A better stand is found on northeast exposures. All of the plants are in good vigor. Quailbush and desert broom are the dominant plants. The furrows have accumulated irrigation water, broke and left large rills on the slopes. The borrow area east of the dike looks about the same as it did in 1981. Bursage and annuals have volunteered. Annuals still grow in the ripper marks, generally.

A good stand of quailbush was found along the top of the dike about 1/4 mile south of Brown Road. Plants growing vigorously on the slope were quailbush, desert broom, triangleleaf bursage and desert saltbush; Australian saltbush is present but plants were severely grazed. The erosion on this section is worse than at other locations. Catesby indicated that this area receives more irrigation water.

The reach north of McKellips Road has only fair cover of triangleleaf bursage, wild buckwheat and desert broom with a good litter of annuals, and erosion is not as severe. Blue, foothill and mexican palo verde were planted along the toe slopes on both sides of the dike. All of the plants are still growing on the downstream side. Plants on the upstream toe are vigorous except those located below the high water line. Blue and foothill palo verde located below the high water line are dead. Mexican palo verde was not affected by floodwater or standing water.

Saguaro and barrel cactus located on the dike near McDowell Road do not look vigorous. Most of the barrel cactus are dead. This is partly due to sprinkle irrigation and damage done by rodents near the base of the plants. The area north of McDowell Road was aerial seeded and not irrigated. The area has an excellent litter cover from annuals. Little erosion was evident.




The survival of palo verde trees on the north and east sides of the entire dike structure, as counted in the field, was 391 found alive and 113 found dead. This indicates a survival rate of 78%. The dead trees were 5 to 10 feet tall and had been flooded. The blue and foothill were affected by standing water but mexican was not affected. The lanscape plan included a total of 547 palo verdes planted, which indicates a survival rate of 72%. The latter is the official survival rate. The south and west sides were not checked - some lost in installation of CAP.

There would be several impacts if irrigation water is removed. They are:

1. Saguaro and barrel cactus will benefit.
2. After the water is removed from the fill there will be a reduction of quailbush and fourwing saltbush. This will be significant within five years.
3. The irrigation water provided on the site has encouraged annuals and a large supply of seed will continue to be available to provide cover with green plants in winter and litter cover in summer.
4. Areas on the dam that have bursage probably will not be affected by removal of irrigation water.
5. The dike has been irrigated long enough that a few riparian plants such as Yerba de pasimo and lotebush have established on the dike. These plants will die when irrigation is discontinued.
6. The erosion rate on the dike will be slowed to a minimum because of less concentration of water and annuals will provide better ground cover than the shrub canopy.
7. The irrigation system has been shut down for two-week time periods or longer and the vegetation was not eliminated.
8. These observations do not evaluate the moisture content of soil material in the dike.

Recommendations:

Discontinue irrigation and allow native plants to adjust to natural rainfall conditions. An acceptable number of plants should survive indefinitely with plants such as saguaro and barrel cactus benefiting. Less erosion will occur, at least on the southeast two miles of fill structure. The entire structure should look similar to the area north of McDowell, as a minimum, as less irrigation water has been available there. This recommendation relates to vegetative cover and erosion only. It does not include impacts on the change in moisture condition of the material in the dike.



Jacob C. Garrison, PMS



Carl E. Pachek, Agronomist

cc: Ralph Arrington, State Engineer, SCS  
Catesby Moore, Maricopa Flood Cont. Dist.





Az.  
BJL

Buckhorn-Mesa: SPOOKHILL FRS

4-10-84

% Moisture Near Sta. 280+00  
Sta. 286+90

1 1



*Joe U.*

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location MESA, ARIZONA - SPOOKHILL FRS Owner MARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date 22 JULY 1978  
 Watershed BUCKHORN MESA Sub-watershed \_\_\_\_\_ Site No. \_\_\_\_\_  
 Contractor MARDIAN CONSTRUCTION CO. Contract No. FCD-77-2-1 Report period: From 7 JULY 1978 to 27 JULY 1978

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% FINES	Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance Rt. or Lt. of C.	Elev.									
34-1	7 JULY	DAM	277+00	10 LT	1578.0	13	12.2	109.7	14.1	115.7	95.0	16.8		JV
35-1	11 JUL	DAM	279+40	35 LT	1575.0	16	8.6	129.6	11.0	124.0	103.8	22.4	ADD MORE MOISTURE	JV
36-1	11 JUL	DAM	279+40	35 LT	1575.0	16	9.7	120.5	11.0	124.9	96.5	22.4		JV
37-1	12 JUL	DAM	274+25	7 LT	1582.9	8.1	11.4	113.6	13.1	118.7	95.7	18.0		JV
38-1	12 JUL	DAM	280+25	10 LT	1577.1	13.9	11.0	111.9	13.3	118.2	95.0	20.5		JV
39-1	13 JUL	DAM	263+00	20 RT	1568.5	22.5	8.4	122.8	10.0	129.3	95.0	26.4		JV
40-1	14 JUL	DAM	280+15	5 RT	1579.0	12	10.1	118.3	10.6	124.0	95.0	30.2		JV
41-1	17 JUL	DAM	277+00	10 RT	1585.5	5.5	8.6	123.8	9.6	126.8	97.6	33.8		JV
42-1	19 JUL	DAM	270+00	12 LT	1581.8	9.2	8.5	122.7	9.6	128.1	95.8	16.1		JV
43-1	18 JUL	DAM	285+00	13 LT	1584.8	6.2	11.3	117.3	10.9	123.4	95.1	20.2		JV
44-1	19 JUL	DAM	266+65	11 RT	1584.4	6.6	7.4	125.0	8.7	130.7	95.6	19.3		JV
45-1	20 JUL	DAM	263+00	15 RT	1572.7	18.3	9.6	128.9	11.4	124.8	103.3	18.7		JV
46-1	24 JUL	DAM	285+00	7 LT	1587.7	3.3	8.5	122.3	10.5	128.8	95.0	16.4		JV
47-1	25 JUL	DAM	257+95	15 RT	1572.2	19.0	8.5	118.2	10.3	124.8	95.0	25.5		JV
48-1	25 JUL	DAM	254+65	20 RT	1572.9	18.1	6.2	104.2	10.0	127.9	81.5	24.0	RECOMPACT & ADD MOISTURE	JV
49-1	26 JUL	DAM	254+65	20 RT	1572.9	18.1	9.6	121.2	10.0	127.9	95.0	24	RETEST OF TEST 48-1	JV
50-1	26 JUL	DAM	252+15	25 RT	1572.8	18.8	12.0	118.1	10.8	125.0	95.0	24.7		JV
51-1	27 JUL	DAM	275+00		1590.1	1.0	8.0	132.7	10.0	125.7	105.6	30.5		JV

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location MEBA, ARIZONA - SPOONHILL FRS Owner MARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date JULY 7 1978  
 Watershed BUCKHORN MEBA Sub-watershed \_\_\_\_\_ Site No. 1  
 Contractor RANDIAN CONSTRUCTION Co. Contract No. FCD-77-2-1 Report period: From 19 JUNE 1978 to 6 JULY 1978

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% Comp. Spec.	FINES Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance Rt. or Lt. of C	Elev.									
21-1	6/20/78	DAM	279+10	10 LT 9.13	1559.7	#4	7.6	129.5	9.5	128.9	100.5	28.0	JV	
22-1	6/20/78	DAM	279+73	9 29	1562.1	#4	10.7	115.4	12.5	120.9	95.5	20.9	JV	
23-1	6/21/78	DAM	279+23	25 RT 27	1564.0	#4	10.2	123.1	10.6	123.5	99.0	28.6	JV	
24-1	6/23/78	DAM	278+00	19 RT 20.5	1570.3	#4	11.0	120.7	10.7	126.6	92.3	24.0	JV	
25-1	6/26/78	DAM	273+00	32 RT 15	1576.0	#4	8.1	124.1	10.1	128.9	97.0	33.1	JV	
26-1	6/27/78	DAM	276+00	30 LT 17.3	1573.7	#4	11.0	104.5	14.1	116.9	89.4	29.5 RECOMPACT & ADD MOISTURE	JV	
27-1	6/27/78	DAM	276+00	30 LT 9	1573.7	#4	12.1	113.55	14.1	116.9	97.1	29.5 ENTRY OF 26-1	JV	
28-1	6/27/78	DAM	276+40	40 LT 16.5	1574.3	#4	9.0	123.6	11.0	126.6	97.6	30.7	JV	
29-1	6/29/78	DAM	268+65	30 RT 9	1562.8	#4	11.1	118.2	11.5	126.8	95.0	27.1	JV	
30-1	6/30/78	DAM	279+35	25 RT 17.1	1573.9	#4	11.0	118.8	13.0	119.0	99.8	24.8	JV	
31-1	7/6/78	DAM	287+00	35 RT 9	1574.8	#4	6.5	119.5	8.7	128.8	92.0	27.6 RECOMPACT & ADD MOISTURE	JV	
32-1	7/6/78	DAM	288+00	35 RT 9	1574.3	#4	7.6	125.9	9.2	127.8	98.5	31.6	JV	
33-1	7/6/78	DAM	287+00	35 RT 9	1574.8	#4	8.0	121.9	8.7	128.8	92.0	27.6 ENTRY OF 31-1	JV	

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location SPARK HILL PDS Owner PARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date JUNE 16 19 70  
 Watershed SOIL CONSERVATION SERVICE Sub-watershed \_\_\_\_\_ Site No. 163  
 Contractor PARISIAN Contract No. PCD-77-3-1 Report period: From 2 June 19 70 to 16 June 19 70

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% Comp. Spec.	Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance Rt. or Lt. of C.	Elev.									
16-1	6/2/70	Dam	283+00	10° RT E	1974.9		10.2	120.6	10.7	127.1	95.0	22.1	RETEST OF 14-1	JV
17-1	6/2/70	Dam	289+00	8 LT E	1982.0		15.9	106.1	15.3	110.7	95.9	23.4		JV
18-1	6/6/70	Dam	290+00	20 LT E	1980.0		11.0	119.2	11.0	123.4	95.0	29.5		JV
19-1	6/8/70	Dam	284+00	15 LT E	1981.0		9.8	125.5	9.6	124.3	100.9	30.6		JV
1-3	6/9/70	Ramp	14+80	40 LT E	1970.6		14.2	110.9	15.7	113.6	97.6	24.4		JV
2-3	6/12/70	Ramp	17+93	47 RT E	1970.9		11.2	122.9	10.2	126.1	95.9	29.0		JV
3-3	6/12/70	Ramp	14+93	28 LT E	1974.2		9.1	127.2	11.1	122.0	104.3	27.7		JV
4-3	6/13/70	Ramp	14+80	25 RT E	1975.9		12.2	117.1	11.9	121.8	96.1	32.2		JV
5-3	6/13/70	Ramp	15+17	9 RT E	1976.4		13.8	124.3	16.8	111.1	111.9	21.5	ADD MOISTURE	JV
6-3	6/13/70	Ramp	15+82	25 LT E	1976.8		12.0	122.2	9.9	126.2	95.3	28.84		JV
7-3	6/13/70	Ramp	14+00	28 LT E	1975.3		9.9	135.1	11.5	123.5	109.4	32.0		JV
8-3	6/13/70	Ramp	13+30	E	1974.4		12.6	118.1	14.5	116.9	101.8	25.9		JV
9-3	6/14/70	Ramp	15+17	5 RT E	1976.4		15.2	114.6	16.8	111.1	103.1	21.9	RETEST OF 8-3	JV
20-1	6/14/70	Dam	181+00	E	1990.0		13.2	119.9	11.3	123.6	97.0	28.0		JV
10-1	6/15/70	Ramp	14+80	E	1976.8		13.5	104	13.5	117.7	88.4	22.9	RECOMPACT	JV
11-1	6/15/70	Ramp	16+17	20 LT E	1981.7		9.7	112.9	10.5	126.3	89.4	22.4	RECOMPACT	JV
12-1	6/15/70	Ramp	14+80	E	1976.8		12.7	117.9	13.5	117.7	100.2	22.5		JV
13-1	6/15/70	Ramp	16+17	20 LT E	1981.7		12.5	120.4	10.5	126.3	95.3	22.6		JV



---

Subject: ENG-Meeting on the need to Continue Irrigation  
Spookhill FRS for Vegetation and Cracking

Date: March 20, 1984

To:

Files

File Code:

210

The meeting was called to order at 9:00 a.m. Tuesday March 20, 1984 by Bob Payette in the Flood Control District's small conference room. The list of participants is attached.

Bob Payette stated the aim of the meeting was to determine the need for future irrigation of the Spookhill FRS to maintain the vegetation and prevent cracking.

The Flood Control District has drilled some auger holes at station 286+90 (non-irrigated) and at station 280+00 (irrigated). The holes were drilled at three locations at each station and samples were taken at 2.5 foot depths. Moisture contents were run on all samples. The data is attached. The amount of water used for irrigation from 1980 to the present time with costs was listed and is attached.

Catesby Moore stated the vegetation south of McDowell Road was very lush, green and of the perennial variety due to the soil type (loamy sand) and the irrigation. Annual varieties of plants are almost non-existent. The vegetation north of McDowell Road is not as lush and has more annual plants and less perennial varieties due to the soil type (sandy loam) and the irrigation. In the non-irrigated area the vegetation is predominately annuals.

The slope erosion measured an average of 30% loss in the irrigated areas and an average of 2% loss in the non-irrigated. The erosion was caused by normal rainfall.

Subsidence surveys need to be rerun by the SCS as soon as possible. Ralph would see if SCS could pay the FCD to run the surveys due to SCS work load at present time.

SCS would check testing records for construction moisture contents and shrinkage limits. If more drilling and testing need be done then guidelines of location, depth, moisture content, shrinkage limit, etc. will have to be given to acquire the needed information required.

A report will be written of findings and conclusions after all data gathering has been completed.



The renovation of the pumphouse will be delayed to determine the need if any.

Dan Lawrence ADWR agreed to review the design features of Spookhill to determine these items positive and negative that may be of concern in determining the irrigation of the dam.

  
Ralph M. Arrington  
State Conservation Engineer

cc: Jack Stevenson  
Wayne Killgore  
Steve Revie  
Joe Knisley



RESULTS OF TWO SEPARATE SETS OF MOISTURE CORE BORINGS AT SPOOKHILL IN IRRIGATED AND NONIRRIGATED AREAS.

Station 286+90 "A"

Station 280+00 "B"

NONIRRIGATED \*

IRRIGATED \*\*

DEPTH IN FT	MOISTURE CONTENT %
1.0	3.4
2.5	3.7
5.0	4.2
7.5	4.9
10.0	5.8
12.5	3.0
15.0	1.2

DEPTH IN FT	MOISTURE CONTENT %
2.5-3.5	5.7
5.0-6.0	7.6
7.5-8.5	3.6
10.0-11.0	7.5
12.5-13.5	9.9
15.0-16.0	7.7
17.5-18.5	10.0
20.0-21.0	8.8

#1

side slope of dam

1.0	1.9
2.5	2.6
5.0	4.1
7.5	4.0
10.0	3.5
12.5	3.6

0.0-1.5	5.5
5.0-6.0	9.6
7.5-8.5	8.9
10.0-11.0	7.3
12.5-13.5	8.9
15.0-16.0	7.0
17.5-18.5	8.6
20.0-21.0	7.6

#2

toe of dam


1.0	5.3
2.5	4.3
5.0	3.1
7.5	5.4
10.0	5.7
12.5	3.8
15.0	3.9
17.5	4.2
20.0	5.7

2.5-4.0	6.4
5.0-6.0	8.3
7.5-8.5	8.2
10.0-11.0	8.9

#3

\* Core boring and moisture determinations by Maricopa County Highway Soils Lab using an Auger drill method.

\*\* Core boring and moisture determinations by Western Technologies using methods similar to the above (as observed by FCD personnel).



## SPOOKHILL WATER BILLS

Meter read date	amount water (in 1,000 of gallons)	Cost
12/28/83	1,165	663.28
11/29/83	983	564.86
10/29/83	1,014	581.62
9/30/83	1,099	627.59
8/30/83	768	448.58
8/03/83	125	86.64
7/29/83	1,408	794.70
7/14/83	166	109.02
Fiscal 83-84 Totals	7,827	4,503.88
6/29/83	1,167	613.02
6/23/83	9	11.51
5/26/83	1,769	913.53
4/27/83	1	39.42
3/30/83	-	39.42
2/23/83	-	37.90
1/26/83	12	37.90
12/29/82	8	37.90
11/24/82	286	169.26
10/27/82	450	247.50
9/30/82	557	299.34
8/31/82	606	325.82
7/30/82	726	380.46
Fiscal 82-83 Totals	5,591	3,152.98
6/28/82	1,092	524.70
5/28/82	1,818	851.40
4/27/82	1,114	534.60
3/29/82	972	470.70
2/24/82	1,117	535.92
1/25/82	1,265	602.55
12/23/81	1,143	547.65
11/23/81	624	314.10
10/21/81	727	360.45
9/22/81	2,032	947.70
8/21/81	2,256	1,048.50
7/28/81	2,038	950.40
6/23/81	1,492	641.88
Fiscal year 81-82 Totals	17,690	8,330.55
5/27/81	2,176	922.32
4/23/81	1,047	459.43
3/27/81	1,154	503.30
2/24/81	417	201.13
1/29/81	909	402.85
12/23/80	652	297.48
11/25/80	1,182	514.78
1/27/80	2,376	1,004.32
9/29/80	1,653	1,182.26
8/22/80	480	226.96
7/24/80	748	336.84
Fiscal year 80-81 Totals	12,794	6,051.67

*Joe V.*

*Sta 280+00*  
~~*Sta 265+00*~~

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location MESA, ARIZONA - SPOOKHILL FRS Owner MARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date 22 JULY 1978  
Watershed BUCKHORN MESA Sub-watershed \_\_\_\_\_ Site No. \_\_\_\_\_  
Contractor MARDIAN CONSTRUCTION Co. Contract No. FCD-77-2-1 Report period: From 7 JULY 1978 to 27 JULY 1978

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% FINES	Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance RT. or LT. of C.	Elev.									
34-1	7 JULY	DAM	277+00	10 LT	1578.0	13	12.2	109.7	14.1	115.7	95.0	16.8		JV
35-1	11 JUL	DAM	279+40	35 LT	1575.0	16	8.6	129.6	11.0	124.0	103.8	22.4	ADD MORE MOISTURE	JV
36-1	11 JUL	DAM	279+40	35 LT	1575.0	16	9.7	120.5	11.0	124.0	96.5	22.4		JV
37-1	12 JUL	DAM	274+25	7 LT	1592.9	8.1	11.4	113.6	13.1	118.7	95.7	18.0		JV
38-1	12 JUL	DAM	280+25	10 LT	1577.1	13.9	11.0	111.9	13.3	118.2	95.0	20.5		JV
39-1	13 JUL	DAM	263+00	20 RT	1568.5	22.5	8.4	122.8	10.0	129.3	95.0	26.4		JV
40-1	14 JUL	DAM	280+45	5 RT	1579.0	12	10.1	118.3	10.6	124.0	95.0	30.2		JV
41-1	17 JUL	DAM	277+00	10 RT	1585.5	5.5	8.6	123.8	9.6	126.8	97.6	33.8		JV
42-1	19 JUL	DAM	270+00	12 LT	1581.8	9.2	8.5	122.7	9.6	128.1	95.8	16.1		JV
43-1	18 JUL	DAM	285+00	13 LT	1584.8	6.2	11.3	117.3	10.9	123.4	95.1	20.2		JV
44-1	19 JUL	DAM	266+65	11 RT	1584.4	6.4	7.4	125.0	8.7	130.7	95.6	19.3		JV
45-1	20 JUL	DAM	263+00	15 RT	1572.7	18.3	9.6	128.9	11.4	124.8	103.3	18.7		JV
46-1	24 JUL	DAM	285+00	7 LT	1587.7	3.3	8.5	122.3	10.5	128.8	95.0	16.4		JV
47-1	25 JUL	DAM	257+95	15 RT	1572.2	11.0	8.5	118.2	10.3	124.8	95.0	25.5		JV
48-1	25 JUL	DAM	254+65	20 RT	1572.9	15.1	6.2	104.2	10.0	127.9	81.5	24.0	RECOMPACT & ADD MOISTURE	JV
49-1	26 JUL	DAM	254+65	20 RT	1572.9	18.1	9.6	121.2	10.0	127.9	95.0	24	RETEST OF TEST 48-1	JV
50-1	26 JUL	DAM	252+15	25 RT	1572.8	18.8	12.0	118.1	10.8	125.0	95.0	24.7		JV
51-1	27 JUL	DAM	275+00		1590.1	10	11.1	137.7	10.0	125.7	105.6	30.5		JV

sta 280+00  
~~sta 285+00~~

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location MESA, ARIZONA - SPOCKHILL FR5  
Watershed BLACKHORN MESA  
Contractor PACIFIC CONSTRUCTION Co.

Owner MARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date JULY 7 1978  
Sub-watershed \_\_\_\_\_ Site No. 1  
Contract No. FCD-77-3-1 Report period: From 19 JUN 1978 to 6 JULY 1978

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% Comp. Spec.	FIELD Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance Rt. or Lt. of C	Elev.									
21-1	6/20/78	DAM	279+10	10 LT C 213	1559.7	#4	7.6	129.5	9.5	128.9	100.5	28.0	JV	
22-1	6/20/78	DAM	279+73	C 29	1542.1	#4	10.7	115.4	12.5	120.8	95.5	20.8	JV	
23-1	6/21/78	DAM	279+25	25 RT C 27	1554.0	#4	10.2	125.1	10.6	125.5	99.0	29.6	JV	
24-1	6/23/78	DAM ✓	279+00	15 RT C 20.5	1570.3	#4	11.0	120.7	10.7	126.6	95.5	24.0	JV	
25-1	6/26/78	DAM ✓	275+00	32 RT C 150	1576.0	#4	8.1	124.1	10.1	126.9	97.8	33.1	JV	
26-1	6/27/78	DAM ✓	276+00	30 LT C 173	1573.7	#4	11.0	104.5	14.1	116.9	89.4	29.5	EXTRACT A AND MOISTURE	
27-1	6/27/78	DAM ✓	276+00	30 LT C 173	1573.7	#4	12.1	113.55	14.1	116.9	97.1	29.5	EXTRACT OF 26-1	
28-1	6/27/78	DAM ✓	276+40	40 LT C 16.5	1574.2	#4	9.0	125.6	11.0	126.6	97.6	30.7	JV	
29-1	6/29/78	DAM	268+05	30 RT C	1562.6	#4	11.1	118.2	11.5	124.8	95.0	27.1	JV	
30-1	6/30/78	DAM	279+35	25 RT C 171	1573.9	#4	11.0	118.8	13.0	119.0	99.8	24.8	JV	
31-1	7/6/78	DAM	287+00	35 RT C 16.2	1574.8	#4	6.5	119.3	8.7	128.8	92.0	27.6	EXTRACT A AND MOISTURE	
32-1	7/6/78	DAM	289+00	35 RT C	1574.3	#4	7.6	125.9	9.2	127.8	98.5	31.6	JV	
33-1	7/6/78	DAM	287+00	35 RT C 16.2	1574.8	#4	8.0	121.9	8.7	128.8	95.0	27.6	EXTRACT OF 31-1	

Sta ~~280+00~~  
Sta ~~265+00~~

SCS-ENG-532  
Rev. 9-70  
File Code ENG-13

Lab copy U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

WEEKLY SUMMARY OF DENSITY DETERMINATIONS

Location SPRING HILL PMS Owner MARICOPA FLOOD CONTROL DISTRICT Submitted By: J. VALENZUELA Date JUNE 16 19 70  
Watershed SOIL CONSERVATION SERVICE Sub-watershed \_\_\_\_\_ Site No. 163  
Contractor MARICOPA Contract No. FCB-77-3-1 Report period: From 2 JUNE 19 70 to 16 JUNE 19 70

Test No.	Date of Test	Location of Sample				Particle Control Size	Corr. % Moist.	Dry Density Lbs/C.F.	Opt. Moist. %	Max. Dry Density Lbs/C.F.	% Comp.	% Comp. Spec.	Instructions to Contractor	Tested By
		From (Dam, Core, etc.)	Sta. No.	Distance Rt. or Lt. of C.	Elev.									
16-1	6/2/70	BAN	(283+00)	10° RT E	1574.5	10.2	120.6	10.7	127.1	93.0	22.1	RETEST OF 14-1	JV	
17-1	6/2/70	BAN	288+00	8 LT E	1582.0	19.9	106.1	15.3	110.7	95.9	23.4		JV	
18-1	6/6/70	BAN	290+00	20 LT E	1580.0	11.0	119.2	11.0	129.4	95.0	29.5		JV	
19-1	6/8/70	BAN	(284+00)	15 LT E	1581.0	9.8	125.9	9.6	124.3	100.9	30.4		JV	
1-3	6/9/70	RAMP	14+80	40 LT E	1570.6	14.2	110.9	15.7	113.6	97.6	24.4		JV	
2-3	6/12/70	RAMP	17+95	47 RT E	1570.9	11.2	122.9	10.2	128.1	95.9	29.0		JV	
3-3	6/12/70	RAMP	14+95	29 LT E	1574.2	9.1	127.2	11.1	122.0	104.3	27.7		JV	
4-3	6/13/70	RAMP	14+40	25 RT E	1575.9	12.2	117.1	11.9	121.8	96.1	32.2		JV	
5-3	6/13/70	RAMP	15+17	5 RT E	1576.4	13.8	124.3	16.8	111.1	111.9	21.5	ADD MOISTURE	JV	
6-3	6/13/70	RAMP	15+82	25 LT E	1576.8	12.0	122.2	9.9	128.2	95.3	28.8		JV	
7-3	6/13/70	RAMP	14+00	28 LT E	1575.3	9.9	135.1	11.9	125.9	109.4	32.0		JV	
8-3	6/13/70	RAMP	13+20	E	1574.4	12.6	118.1	14.5	116.0	101.8	25.6		JV	
9-3	6/14/70	RAMP	15+17	5 RT E	1576.4	15.2	114.6	16.8	111.1	105.1	21.5	RETEST OF 503	JV	
20-1	6/14/70	BAN	181+00	E	1590.0	13.2	119.9	11.3	123.6	97.0	28.0		JV	
10-1	6/15/70	RAMP	14+80	E	1576.8	13.3	104	13.5	117.7	89.4	22.5	RECOMPACT	JV	
11-1	6/15/70	RAMP	16+17	20 LT E	1581.7	9.7	112.9	10.5	126.3	89.4	22.4	RECOMPACT	JV	
12-1	6/15/70	RAMP	14+80	E	1576.8	12.7	117.9	13.5	117.7	100.2	22.5		JV	
13-1	6/15/70	RAMP	16+17	20 LT E	1581.7	12.5	120.4	10.9	126.3	95.3	22.4		JV	

RESULTS OF TWO SEPARATE SETS OF MOISTURE CORE BORINGS AT SPOOKHILL IN IRRIGATED AND NONIRRIGATED AREAS.

NONIRRIGATED * Sta 286 + 90		IRRIGATED ** Sta 280 + 00	
DEPTH IN FT	MOISTURE CONTENT %	DEPTH IN FT	MOISTURE CONTENT %
1.0	3.4	2.5-3.5	5.7
2.5	3.7	5.0-6.0	7.6
5.0	4.2	7.5-8.5	3.6
7.5	4.9	10.0-11.0	7.5
10.0	5.8	12.5-13.5	9.9
12.5	3.0	15.0-16.0	7.7
15.0	1.2	17.5-18.5	10.0
		20.0-21.0	8.8
side slope of dam			
1.0	1.9	0.0-1.5	5.5
2.5	2.6		
5.0	4.1	5.0-6.0	9.6
7.5	4.0	7.5-8.5	8.9
10.0	3.5	10.0-11.0	7.3
12.5	3.6	12.5-13.5	8.9
		15.0-16.0	7.0
		17.5-18.5	8.6
		20.0-21.0	7.6
toe of dam			
1.0	5.3		
2.5	4.3	2.5-4.0	6.4
5.0	3.1	5.0-6.0	8.3
7.5	5.4	7.5-8.5	8.2
10.0	5.7	10.0-11.0	8.9
12.5	3.8		
15.0	3.9		
17.5	4.2		
20.0	5.7		

\* Core boring and moisture determinations by Maricopa County Highway Soils Lab using an Auger drill method.

\*\* Core boring and moisture determinations by Western Technologies using methods similar to the above (as observed by FCD personnel).



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

Flood Control District of Maricopa County  
3335 West Durango Avenue  
Phoenix, Arizona 85009

May 19, 1983

Attn: Mr. Robert Payette

Re: Spook Hill Dam

Job No. 2183J011

Dear Mr. Payette,

Thank you for your patience on this project and we look forward to working for you again. The last time that the driller went out he took samples of the other three borings and if you require moisture content testing on those samples please contact me.

Respectfully submitted,

WESTERN TECHNOLOGIES, INC.

*Gabriel R Escamillo Jr*

Gabriel Escamillo

mb

Attachment

Copies to: Addressee (1)

SPOOK HILL DAM

JOB NO. 2183J011

*drill at*

*280+00*

<u>TEST BORING NUMBER</u>	<u>DEPTH (FEET)</u>	<u>MOISTURE CONTENT %</u>
1	2½ - 3½	5.7
1	5 - 6	7.6
1	7½ - 8½	3.6
1	10 - 11	7.5
1	12½ - 13½	9.9
1	15 - 16	7.7
1	17½ - 18½	10.0
1	20 - 21	8.8
2	0 - 1½	5.5
2	5 - 6	9.6
2	7½ - 8½	8.9
2	10 - 11	7.3
2	12½ - 13½	8.9
2	15 - 16	7.0
2	17½ - 18½	8.6
2	20 - 21	7.6
3	2½ - 4	6.4
3	5 - 6	8.3
3	7½ - 8½	8.2
3	10 - 11	8.9



## SPOOKHILL WATER BILLS

Meter read date	amount water (in 1,000 of gallons)	Cost
12/28/83	1,165	663.28
11/29/83	983	564.86
10/29/83	1,014	581.62
9/30/83	1,099	627.59
8/30/83	768	448.58
8/03/83	125	86.64
7/29/83	1,408	794.70
7/14/83	166	109.02
Fiscal 83-84 Totals	7,827	4,503.88
6/29/83	1,167	613.02
6/23/83	9	11.51
5/26/83	1,769	913.53
4/27/83	1	39.42
3/30/83	-	39.42
2/23/83	-	37.90
1/26/83	12	37.90
12/29/82	8	37.90
11/24/82	286	169.26
10/27/82	450	247.50
9/30/82	557	299.34
8/31/82	606	325.82
7/30/82	726	380.46
Fiscal 82-83 Totals	5,591	3,152.98
6/28/82	1,092	524.70
5/28/82	1,818	851.40
4/27/82	1,114	534.60
3/29/82	972	470.70
2/24/82	1,117	535.92
1/25/82	1,265	602.55
12/23/81	1,143	547.65
11/23/81	624	314.10
10/21/81	727	360.45
9/22/81	2,032	947.70
8/21/81	2,256	1,048.50
7/28/81	2,038	950.40
6/23/81	1,492	641.88
Fiscal year 81-82 Totals	17,690	8,330.55
5/27/81	2,176	922.32
4/23/81	1,047	459.43
3/27/81	1,154	503.30
2/24/81	417	201.13
1/29/81	909	402.85
12/23/80	652	297.48
11/25/80	1,182	514.78
1/27/80	2,376	1,004.32
9/29/80	1,653	1,182.26
8/22/80	480	226.96
7/24/80	748	336.84
Fiscal year 80-81 Totals	12,794	6,051.67



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

Flood Control District of Maricopa County  
3335 West Durango Street  
Phoenix, Arizona 85009

October 11, 1984

Attn: Mr. Nick Karan, P.E.

Re: Shrinkage Limit Tests  
Spook Hill Dam

Job No. 2184J017

Shrinkage limit tests were conducted according to ASTM Designation D427-83 which states that the initial water content for the test should be equal or slightly greater than the liquid limit. Using this procedure often results in shrinkage limit values greater than the plastic limit for sandy and silty clays (Holtz and Kovacs).

The soils tested were silty or clayey sands with 20.5% to 35.3% passing the 200 mesh sieve. High shrinkage limit values could be expected for soils that are predominately sands. The grain to grain contact would occur primarily between sand particles and the size of capillaries that produce tension upon drying would be relatively large in diameter. Capillary tension and resulting shrinkage would be low; therefore, little shrinkage would occur and the shrinkage limit would be high.

Shrinkage limit test results are meaningful only for clays and published interpretations may be applied only to clay soils. For clays, Holtz and Gibbs present the following information for arid region soils: A shrinkage limit greater than 12 has little volume change potential. Bowles says that it is not possible to quantify the term "little volume change potential".


References:

Holtz and Kovacs, "An Introduction to Geotechnical Engineering", 1981, Prentice-Hall, pages 178-185

Bowles, "Physical and Geotechnical Properties of Soils", 1979, McGraw-Hill, pages 223-225.

We hope this information assist you in the interpretation of the attached test results. If we may be of further service please don't hesitate to contact us.

Respectfully submitted,  
WESTERN TECHNOLOGIES INC.

  
John C. Rosner, Ph.D., P.E.

nj

Attachments

Copies to: Addressee (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 1 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 265-6.6 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
3"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2 1/2"			
2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1 1/2"			
1"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
3/4"			
1/2"			Other: Moisture Content, % ASTM D2216 7.4
3/8"			
1/4"			Shrinkage Limit, % ASTM D427 12.6
No. 4			
8			
10			
16			
30			
40			
50			
100			
200	35.3		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 2 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84  
Type of Material -- Submitted By WTI Date 8/29/84  
Source of Material Station 265-9.2 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2 1/2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1 1/2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
3/4"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
1/2"			
3/8"			Other: Moisture Content, % ASTM D2216 7.8
1/4"			
No. 4			Shrinkage Limit, % ASTM D427 22.7
8			
10			
16			
30			
40			
50			
100			
200	30.4		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 3 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date \_\_\_\_\_  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona Sampled By WTI Date 8/28/84

Type of Material -- Submitted By WTI Date 8/29/84

Source of Material Station 265-16.2 Authorized By FCD/Karan Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2 1/2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1 1/2"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
1"			
3/4"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
1/2"			
3/8"			Other: Moisture Content, % ASTM D2216 7.8
1/4"			
No. 4			Shrinkage Limit, % ASTM D427 25.7
8			
10			
16			
30			
40			
50			
100			
200	28.9		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 4 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 265-18.3      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      8.3
¼"			
No. 4			Shrinkage Limit, % ASTM D427      22.7
8			
10			
16			
30			
40			
50			
100			
200	20.5		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 5 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam  
Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 265-22.5      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- LL = _____ PI = _____
2½"			
2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
1½"			
1"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- Specific Gravity _____
¾"			
½"			Resistance 'R' Value of Compacted Soils ASTM D2844- 'R' Value _____
⅜"			
¼"			Other: Moisture Content, % ASTM D2216 7.1
No. 4			
8			Shrinkage Limit, % ASTM D427 25.5
10			
16			
30			
40			
50			
100			
200	21.0		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 6 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 280-5.5      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      5.8
¼"			
No. 4			Shrinkage Limit, % ASTM D427      21.3
8			
10			
16			
30			
40			
50			
100			
200	20.9		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 7 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84

Type of Material --      Submitted By WTI      Date 8/29/84

Source of Material Station 280-12.0      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations Maximum Dry Density, pcf _____ Optimum Moisture, % _____ <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      5.4
¼"			
No. 4			Shrinkage Limit, % ASTM D427      18.6
8			
10			
16			
30			
40			
50			
100			
200	21.7		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 8 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 280-16.0      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424-      LL = _____ PI = _____
2½"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ Maximum Dry Density, pcf _____ Optimum Moisture, % _____
2"			
1½"			Specific Gravity of Soils (minus No. 4 material) ASTM D854-      Specific Gravity _____
1"			
¾"			Resistance 'R' Value of Compacted Soils ASTM D2844-      'R' Value _____
½"			
⅜"			Other: Moisture Content, % ASTM D2216      8.5
¼"			
No. 4			Shrinkage Limit, % ASTM D427      19.9
8			
10			
16			
30			
40			
50			
100			
200	24.5		
Finer than 200 ASTM D1140-			

Copies to: Client (3)



**WESTERN  
TECHNOLOGIES  
INC.**

3737 East Broadway Road  
P.O. Box 21387  
Phoenix, Arizona 85036  
(602) 437-3737

**LABORATORY REPORT**

**PHYSICAL PROPERTIES OF SOILS**

Page 9 of 9

Client Flood Control District  
3335 West Durango Street  
Phoenix, Arizona 85009  
Attn: Mr. Nick Karan

Job No. 2184J017  
Lab/Invoice No. 2184W017  
Date 9/11/84  
Reviewed By \_\_\_\_\_

Project Spook Hill Dam

Location Mesa, Arizona      Sampled By WTI      Date 8/28/84  
Type of Material --      Submitted By WTI      Date 8/29/84  
Source of Material Station 280-20.5      Authorized By FCD/Karan      Date 8/28/84

Sieve Analysis, ASTM D422-

Sieve Size	% Passing Accumulative	Specification	Soil Classification
3"			Liquid Limit and Plasticity of Soils ASTM D424- <span style="float: right;">LL = _____ PI = _____</span>
2 1/2"			
2"			Moisture - Density Relations <input type="checkbox"/> ASTM D698- ; <input type="checkbox"/> ASTM D1557- ; Method _____ <span style="float: right;">Maximum Dry Density, pcf _____ Optimum Moisture, % _____</span>
1 1/2"			
1"			Specific Gravity of Soils (minus No. 4 material) ASTM D854- <span style="float: right;">Specific Gravity _____</span>
3/4"			
1/2"			Resistance 'R' Value of Compacted Soils ASTM D2844- <span style="float: right;">'R' Value _____</span>
3/8"			
1/4"			Other: Moisture Content, % ASTM D2216 <span style="float: right;">9.7</span>
No. 4			
8			Shrinkage Limit, % ASTM D427 <span style="float: right;">26.1</span>
10			
16			
30			
40			
50			
100			
200	32.6		
Finer than 200 ASTM D1140-			

Copies to: Client (3)